

**TENDER DOCUMENT No.-06 (S. No-06)****लखनऊ विकास प्राधिकरण
निविदा-प्रपत्र**

1. कार्य का नाम: बसन्तकुज योजना स्थित प्राधिकरण कैम्प कार्यालय के बाहर औद्योगिक सौन्दर्यीकरण एवं नर्सरी निर्माण का कार्य।

2.

कार्य का नाम	बी0ओ0क्यू0 धनांक (रु0)	प्रतिभूति धनराशि (रु0)	समय	श्रेणी	निविदा मूल्य (रु0)
बसन्तकुज योजना स्थित प्राधिकरण कैम्प कार्यालय के बाहर औद्योगिक सौन्दर्यीकरण एवं नर्सरी निर्माण का कार्य।	4,55,341.00	22,800.00	01 माह	डी/सिंगल बिड	650.00 +18% GST

3. निविदा प्रपत्र निविदा सूचना में दी गई अवधि में वेबसाइट अथवा "http://www.ldaonline.in" से डाउन-लोड किये जायेंगे तथा पूर्ण रूप से भरे हुए एवं हस्ताक्षरित निविदाएं सीलबन्द लिफाफे में निविदा सूचना में अंकित तिथियों को निर्धारित स्थान-आयुक्त, लखनऊ मण्डल के नजारत कक्ष, लखनऊ कार्यालय, जिलाधिकारी, लखनऊ कार्यालय के कलेक्ट्रेट स्थित कक्ष संख्या-25 तथा प्राधिकरण के नवीन भवन, गोमती नगर, लखनऊ में रखे निविदा बाक्स में डाले जा सकेंगे।
4. निविदा के साथ दी जाने वाली प्रतिभूति की धनराशि, कार्य पूर्ण करने हेतु निर्धारित समय, कार्य की श्रेणी व अन्य शर्तें एवं विवरण निविदा सूचना में अंकित शर्तों, विवरण एवं 'नोट' के अनुसार लागू होगी। निविदा सूचना निविदा प्रपत्र का एक अंश है।
5. समस्त निविदाओं हेतु प्रतिभूति की धनराशि अधिशासी अभियंता, ल0वि0प्रा0 को न्यस्त एन.एस.सी./एफ.डी. आर./एन.एस.एस. के रूप में जमा करना होगा। यदि किसी निविदा के साथ उक्त प्रतिभूति धनराशि जमा नहीं होगी, तो ऐसी निविदाएं खोलते ही पुनः सील कर दी जाएंगी।
6. ठेकेदारों के चालित देयको से 10 प्रतिशत उस समय तक काटा जाएगा जब तक कि बकाया 5 प्रतिशत जमानत का धन प्राप्त नहीं हो जाता है वह 5 प्रतिशत अन्तिम देयक में ठेकेदार को दे दिया जायेगा तथा 5 प्रतिशत कार्य सन्तोषजनक होने के बाद 12 माह बाद अनुरक्षण अवधि समाप्त होने के बाद वापस किया जायेगा।
7. किसी भी अथवा समस्त निविदाओं को अस्वीकृत कर देने का अधिकार सुरक्षित रहेगा इस सम्बन्ध में किसी भी व्यक्ति तथा व्यक्तियों द्वारा निविदा के अस्वीकृत होने के कारण को पूछा नहीं जा सकता है।
8. निविदा की स्वीकृति प्राप्त करने वाले ठेकेदार को स्वीकृत पत्र प्रमाण लेख पर हस्ताक्षर करने होंगे।
9. किसी भी निविदा पर विचार नहीं किया जायेगा जब तक कि उसके साथ अग्रिम धनराशि जमा करने की रसीद अथवा निविदा सूचना के अनुसार अग्रिम धनराशि संलग्न न होगी।
10. निविदा की दर तथा जोड़ को शब्दों तथा अंकों में स्पष्ट रूप से भरा जायें तथा कोई भी कटिंग व ओवर राइटिंग न की जायेगी अन्यथा निविदा अस्वीकृत कर दी जायेगी।
11. यदि निविदा की स्वीकृति प्राप्त करने वाले ठेकेदार 15 दिन के अन्दर स्पष्ट रूप से कान्ट्रैक्ट पर हस्ताक्षर नहीं करेगा तो निविदा के साथ जमा किया हुआ धन जब्त कर लिया जायेगा तथा निविदा की स्वीकृति वापस कर ली जायेगी।
12. ठेकेदार अपनी निविदा में दर उसी प्रकार से भरेगा जिस प्रकार से निविदा पत्र में मांगी गयी हों।
13. निविदा देने की तिथि से रु0 50,000.00 से कम की निविदा 4 माह तक वैध रहेगी तथा इसके ऊपर के धनराशि की निविदा 6 माह तक वैध रहेगी।
14. जो निविदा पता ठेकेदार का निविदा में मिलेगा वही पता मान्य होगा और इस पते पर भेजी गई डाक यदि डाकखाने से किसी कारण से वितरित न होकर वापस हो जाती है तो समझा जायेगा कि ठेकेदार द्वारा स्वीकार कर ली गई है।
15. प्रत्येक निविदा के साथ अलग से अग्रिम धनराशि होनी चाहिए, दूसरे निविदा के साथ लगी अग्रिम धनराशि मान्य न होगी।
16. पुरानी सिक्क्योरिटी या अग्रिम धनराशि जो विभाग द्वारा वापस की जाती है उसको अग्रिम धन के रूप में इंगित किया जायेगा तो मान्य न होगी।
17. प्रत्येक कार्य के निविदा प्रपत्र की मूल प्रति विभाग में सुरक्षित रखी गयी है। प्राप्त निविदाओं में किसी भी प्रकार की भिन्नता स्वीकार योग्य नहीं होगी एवं विवाद की स्थिति में मूल प्रति ही अंकित होगी।
18. प्रत्येक कार्य की निविदा के लिफाफे पर कार्य का नाम स्पष्ट रूप से अंकित होगी।
19. सभी साधारण एवं विशेष शर्तें/नियमों का पालन न होने पर निविदा मान्य न होगी और ठेकेदार को डिबार कर दिया जायेगा एवं ब्लैक लिस्ट भी किया जा सकता है।

हस्ता0
प्रमाणित —
प्रधान लिपिक {अभि0 विभाग}

ठेकेदार के हस्ताक्षर
तथा पता :

हस्ता0
अधिशासी अभियन्ता
लखनऊ विकास प्राधिकरण



TENDER DOCUMENT No.-06 (S. No-06)

लखनऊ विकास प्राधिकरण

कार्यालय : मुख्य अभियन्ता
लखनऊ विकास प्राधिकरण,
प्राधिकरण भवन, गोमती नगर,
लखनऊ।

संख्या : 06/निविदा/मु0अ0/2024-25

दिनांक : 13/06/2024

—: निविदा सूचना :-

लखनऊ विकास प्राधिकरण में पंजीकृत ठेकेदारों से निम्नलिखित कार्य हेतु मुद्रांकित निविदाएं आमंत्रित की जाती हैं। कार्य के निविदा प्रपत्र वेबसाइट "http://www.lvaonline.in" से डाउनलोड किये जा सकेंगे एवं आयुक्त, लखनऊ मण्डल कार्यालय के नजारत कक्ष, जिलाधिकारी, लखनऊ के कलेक्ट्रेट स्थित कार्यालय के कक्ष संख्या-25 तथा प्राधिकरण के नवीन भवन स्थित निविदा बाक्स में स्तम्भ (8) में अंकित तिथियों में डाले जा सकेंगे अथवा रजिस्टर्ड डाक से अपराह्न 3:00 बजे तक भेजे जा सकते हैं, परन्तु निर्धारित समय के पश्चात् प्राप्त निविदाओं पर विचार नहीं किया जाएगा। प्राप्त निविदाएं, निविदा डालने की अंतिम तिथि को अपराह्न 4:00 बजे ठेकेदारों अथवा उनके अधिकृत प्रतिनिधियों (यदि उपस्थित हुए) के समक्ष प्राधिकरण के नवीन भवन में अधिशासी अभियन्ता कार्यालय कक्ष में खोली जाएंगी।

क्रम सं०	कार्य का नाम	बी0ओ0क्यू0 धनराशि (रु०)	प्रतिभूति धनराशि (रु०)	कार्य पूर्ण करने की अवधि	पंजीकृत श्रेणी	निविदा मूल्य (रु०)	निविदा डालने की अवधि
1	2	3	4	5	6	7	8
1.	बसन्तकुज योजना स्थित प्राधिकरण कैम्प कार्यालय के बाहर औद्यानिक सौन्दर्यीकरण एवं नर्सरी निर्माण का कार्य।	4,55,341.00	22,800.00	01 माह	डी/सिंगल बिड	650.00 +18% GST	14.06.2024 से 24.06.2024 अपराह्न 3:00 बजे तक

नोट :

- समस्त निविदाओं हेतु प्रतिभूति की धनराशि अधिशासी अभियन्ता, ल0वि0प्रा0 को न्यस्त एन.एस.सी./एफ.डी. आर./एन.एस.एस. के रूप में जमा करना होगा। यदि किसी निविदा के साथ उक्त प्रतिभूति धनराशि जमा नहीं होगी, तो ऐसी निविदाएं खोलते ही पुनः सील कर दी जाएंगी।
- निविदा मूल्य नगद/बैंक ड्राफ्ट के रूप में सचिव, लखनऊ विकास प्राधिकरण के पक्ष में देय होगी, जो वापस नहीं होगी।
- निविदा के साथ पंजीकरण के नवीनीकरण की रसीद की छायाप्रति संलग्न करना अनिवार्य होगा।
- सड़क के कार्यों में बिटुमिन के प्रयोग की दशा में बिटुमिन की खरीद का प्रमाण पत्र कार्य के दौरान उपलब्ध कराना होगा। यदि कार्य हॉटमिक्स प्लाण्ट के माध्यम से कराया जाएगा तो बिटुमिन की खरीद का प्रमाण पत्र प्लाण्ट की ओर से दिया जाना अनिवार्य होगा।
- कार्यालय अवकाश की दशा में अगले कार्य दिवस तक निविदा वेबसाइट से लोड की जा सकेगी/डाली जा सकेगी/अगले कार्य दिवस को खोली जाएगी।
- किसी भी निविदा को स्वीकृत अथवा अस्वीकृत करने अथवा विभाजित करने का पूर्ण अधिकार उपाध्यक्ष, लखनऊ विकास प्राधिकरण में निहित होगा।
- अन्य जानकारी अधोहस्ताक्षरी के कार्यालय से ज्ञात की जा सकेगी।

मुख्य अभियन्ता



TENDER DOCUMENT No.-06 (S. No-06)

लखनऊ विकास प्राधिकरण

SCHEDULE 'A'

The work is to be done in connection with.....

.....

The site of work can be ascertained from the Assistant Engineer (Project Lucknow Development Authority, Lucknow).

The tenders are advised to inspect the site of the work
Before tendering the rates so that they may fully acquaint themselves with the nature of the work to be done, the means of communication and availability of materials and water required for the work.

The contractor must complete the work in accordance with the specification and to the entire satisfaction of the Engineer Incharge with the specified period.

SCHEDULE 'B'

The drawings regarding this, this work can be seen in the office of Adhishashi Abhiyanta Lucknow Development Authority on any working day from 10 A.M. to 5 P.M.

SCHEDULE 'C'

-- NIL --

SCHEDULE 'D'

The following samples be submitted by the contractor within 10 days of the receipt of orders to start the work and subsequent supplies shall not be inferior to the samples approved.

1. Bricks	10 Nos.	Surkhi	1Cft.
2. Coarse Sand	1 Cft.	Brick ballast	1 Cft.
3. Local Sand	1 Cft.	Any other sample	Desired by the Engineer
4. Hard stone grit	1 Cft.		

Materials specified by the Engineer from time to time and brought on the site of work shall occasionally be tested by the Engineer at the cost of the Contractor. The material rejected shall be removed by the contractor within 24 hours, failing which the rejected materials shall be removed or disposed of by the Lucknow Development Authority at the cost of the contractor.



TENDER DOCUMENT No.-06 (S. No-06)

लखनऊ विकास प्राधिकरण

SCHEDULE 'I'

1. All materials supplied by the contractor brought on the site shall be tested by the Engineer Incharge frequently to check up if they confirm the specification of P.W.D.
2. All the rates as may be necessary shall be performed at the contractor's expenses and will have to make all necessary arrangements for conducting them and when called upon to do so to the satisfaction of the Engineer.

SCHEDULE 'F'

All works specified herein shall be completed in all respects to the entire satisfaction of the Engineer Incharge and handed over to him or any persons nominated by him to take over within a period ofmonths from the date of receipt of written order to commence the work.

The contractor's responsibility shall, however, not be over until the maintenance period of one year or one rainy season with whichever ever is more from the date of completion is over if any defect is notified at the contractor's cost.

Individual portions of the work may be brought into use by the Lucknow Development Authority as each section is completed but the maintenance period of one year or one rainy season whichever ever is more shall be finally counted from the date of entire work under the contract is finally completed and handed over.



TENDER DOCUMENT No.-06 (S. No-06)

लखनऊ विकास प्राधिकरण

SCHEDULE I

The department will supply the following materials at the rate mentioned against each.

SI. No.	Name of the material	Rate	Place of issue	Remarks
1-	Nil		Nil	
2-	Nil		Nil	

CONDITIONS

1. The Engineer and subordinate incharge shall be free inspect the godown of Contractor at any time.
2. Every effort will be made by the L.D.A. for continuous supply of the above Material but the department dose not guarantee for the same and it will have to be arranged by the contractor without any claim. It should carefulled noted by the contractor that no compensation whatsoever shall be given to them for any interruption in the work for want of supply of material form the L.D.A. or any other case whatsoever.
3. Material issued to the contractor shall be carted by them to the site of work at his own cost.
4. Stores supplied by the department, if found damaged or missing shall be recovered at double the rate of issue. In case of materials supplied free of cast the deductions shall be made at double the book value of the material.
5. Any other material not easily available in the market at the time of construction but existing in the department store can be issued at the store issue rate plus 10% or market rate whichever is higher on the written request of the contractor.
6. The contractor will have to make his own arrangement for the all T.P. machinery and other equipment required to complete the work under his contract.

Contractor.....

Dated.....

Witness.....

Dated.....



TENDER DOCUMENT No.-06 (S. No-06)

लखनऊ विकास प्राधिकरण

LUCKNOW DEVELOPMENT AUTHORITY LUCKNOW

SPECIAL CONDITIONS FOR WORK

All the work shall be carried out as per detailed U.P.P.W.D., U.P. JAL NIGAM, U.P. POWER CORPORATION LTD., M.O.S.T. (Road Wing) specifications for road and bridge work (third revision 1995) as the case may be, latest circulars and instructions issued time to time as per instructions of Engineer-in-charge and other inspecting officers.

EXTENT OF CONTRACT

The Contract comprises construction and completion of the specified job and the provisions of all labour, materials, T&P etc. and transport, temporary works etc. whether of temporary or permanent in nature required for the construction, completion and maintenance of the work.

INSPECTIONS OF THE SITE

The tenderer (s) must inspect and examine the site of work and its surroundings and satisfy himself/themselves before submitting his/their tender. He/they has/have to make sure of the positions of quarries and availability of required material from quarries mentioned in the specifications, topography of the site availability of labour and material and other amenities before tendering. No claim for additional work or extra work due to any of the above will be allowed.

ENTRIES IN TENDER

All entries by the tenderer should be in one ink and one hand/on prescribed bill of quantity only. Erasures and overwriting are not permissible. All corrections should be neatly written and signed by the tenderer. Rate should be written in figures as well as in words. In case there is any variation, lower rate shall be treated as Tender rate.

CONDITIONAL/INCOMPLETE TENDER

Conditional, incomplete, unsigned tenders will not be considered. Only those bidders who supply necessary proof/documents of possession of the required equipments in their bids should be considered as responsive for further evaluation.

ADDRESS OF CONTRACTOR

The contractor shall give his full permanent postal address. The postal receipt of the letters sent to him on this address shall be considered sufficient proof that they have been delivered to him.

ACCEPTANCE OF TENDER

The department shall have the right to accept or reject any or all the tenders or part thereof, without assigning any reason to contractor and no claim whatsoever shall be entertained on this account.



TENDER DOCUMENT No.-06 (S. No-06)

लखनऊ विकास प्राधिकरण

SIGNING OF TENDER DOCUMENTS

Contractor shall sign each page of tender documents before offering his tender and required stamp duty on the contract deed will be borne by the contractor.

COPY OF CONTRACT

On request, the Executive Engineer may furnish the contractor with a copy of the contract.

TIME OF COMPLETION

The time of completion as shown in this tender is for completion of the entire work.

EMPLOYMENT OF LABOUR

The contractor shall submit a daily report to the Engineer-in-charge regarding the total labour employed by him for the work and shall be bound to pay wages which shall not be less than the wages fixed under Minimum Wages Act.

LINE AND LEVELS

The contractor shall be solely responsible for setting out the works and for the correctness of the position, levels, dimensions and alignment according to the specification and shall provide all necessary assistance, instruments, pegs, sticks, poles and other materials, required for the purpose. The tender rates shall be deemed to include all this.

PROGRAMME AND RETURNS TO BE FURNISHED

As soon as practicable, but not later than 7 days after the acceptance of his tender, the contractor shall submit to the Executive Engineer for his approval, a time schedule to carry out works. The contractor shall whenever required by the Engineer-in-charge, furnish for his information arrangements for carrying out the work. The submission to and approval by Engineer-in-charge of such program or furnishing of such particulars shall not relieve the contractor of any of his duties or responsibilities under the contracts. In addition, the contractor shall have to furnish returns of work done by him, as may be directed by the Engineer-in-charge from time to time.

EXECUTION

The contractor shall have to execute various item of works strictly according to the order and time schedule approved by the Executive Engineer. Materials will also be tested for proper grading of Mix by Department before use.

TECHNICAL STAFF AT SITE OF WORK

The contractor shall have to employ full time technical staff for supervision of the work. Name of the technical staff employed by the contractor shall be intimated in writing to the Engineer-in-charge. Any change of technical staff during the execution of work should be intimated immediately in writing to the Engineer-in-charge.



TENDER DOCUMENT No.-06 (S. No-06)

लखनऊ विकास प्राधिकरण

SITE OFFICE

The contractor shall establish and maintain a site office under his authorized representative/technical staff. All relevant documents shall be kept in the site office.

ORDER BOOK

A site order book shall be maintained at the site of work in which instructions shall be given to the contractor as and when necessary. These instruction/orders, shall have to be signed and complied by the Contractor or his authorized representative. The entries in 'Site Order Book' shall be treated as proper notice serving upon the contractor in terms of his contract.

LIGHTING ARRANGEMENT

The contractor shall make his own arrangement for lights during the fag end of the day in case the work is likely to be delayed due to unavoidable circumstances.

TRAFFIC CONTROL

The contractor shall take all measures necessary for the safety of traffic during execution of work and shall provide, erect and maintain such barricades, reflective signs and caution boards, making flags, lights flagmen as necessary or as directed by the Engineer-in-charge for smooth and safe flow of traffic during execution or work. The contractor shall ensure to proper maintenance of pattries in 2.5m. width during execution of the bituminous work and it shall be kept always damp by regularly watering to avoid nuisance. In case of any casualty taking place at the work site, the contractor shall be solely responsible for payment of any compensation etc. to the aggrieved party.

SUSPENSION OF WORK

The contractor on the written order of the Executive Engineer/Assistant Engineer shall suspend the progress of the works or any part thereof, for such time and in such manner as may be considered necessary and during such suspension shall properly protect and secure the work as far as necessary in the opinion of the Executive Engineer. Nothing extra shall be paid to the contractor if such a suspension is necessary for proper execution of the work by reason of weather or by some default or the contractor or necessary for safety of the work or any part thereof.

SAMPLES

Contractor shall make laboratory with sufficient arrangement of testing facilities, appliances and laboratory technicians etc. at site and shall always co-operate in procurement of samples, conduction tests, as may be directed and no extra payment shall be made for them. Test samples shall be taken carefully in accordance with the I.S.I. method of sampling, no plea shall be entertained on this account. Job Mix Formula for B.M. and S.D.B.C. shall be done from any reputed authority by the contractor on his cost.

TESTING MATERIALS

All materials and workmanship shall be of the respective kind described in the contract and in the accordance with Engineer-in-charge instructions and shall be subjected from time to time to the testes mentioned under specifications. The contractor shall provide such assistance, labour and materials as are normally required for examining measuring and testing of the works and quantity weight or quality of materials used and shall supply



TENDER DOCUMENT No.-06 (S. No-06)

लखनऊ विकास प्राधिकरण

materials, sufficiently in advance for testing as mentioned under specifications. The materials used subsequently for execution of the work shall strictly conform to the quality and sample approved. Necessary test for which facilities are not available locally or at site shall be conducted in the nearest available laboratory research institute, Lucknow or any other reputed technical institution. Cost of such testing and forwarding of sample to the laboratory etc. shall be borne by the contractor and nothing extra shall be paid on this account. Regular quality control test registers shall be maintained by the contractor.

ROYALTIES AND TAXES ETC.

The contractor shall pay all royalties, license fee, other charge at quarry, octroi duties, custom duties, toll taxes, trade tax and any other local taxes as may be levied. No passes for octroi or toll levied by local bodies on toll bridges shall be issued by the Department. Rate shall inclusive of the same. Nothing extra shall be paid due to fluctuations in the cost of materials, machines, bitumen, P.O.L., labour and all types of taxes etc.

COMPLIANCE WITH LOCAL BYE LAWS

The contractor shall throughout the continuance of the contract and in respect of all matters arising out of performance thereof, conform with all required regulating and bye-laws of the local or other authorities which may be applicable to the works.

ROAD TRANSPORT

The contractor employing motor vehicles for transport of material shall abide by provisions of the Motor Vehicles Act.

DAMAGES BY RAINS, ACCIDENTS OR NATURAL CALAMITIES

No payment will be made to the contractor for damage caused by rains, accidents or other natural calamities during the progress of work. No claim whatsoever shall be entertained on this account.

DEFAULT OF CONTACTOR IN COMPLIANCE

Constant defiance of the instructions of Engineer-in-charge on the part of the contractor or his authorized agent will make the contract will liable to be terminated.

CLEARANCE OR SITE ON COMPLETION

The contractor shall at all times keep the premises free from accumulated waste materials or rubbish caused by his employees on the works and on completion of the work, he shall clear away and remove from site all surplus materials, rubbish and temporary work of any kind and fill up borrow pits dug by him. He shall leave whole of the site and work clean and in a workmanlike condition to the entire satisfaction of the Engineer-in-charge.



TENDER DOCUMENT No.-06 (S. No-06)

लखनऊ विकास प्राधिकरण
SCHEDULE – 'G'

कार्य का नाम : बसन्तकुज योजना स्थित प्राधिकरण कैम्प कार्यालय के बाहर औद्यानिक सौन्दर्यीकरण एवं नर्सरी निर्माण का कार्य।

S. N.	Item of Work	Unit	Qty	Rate
1	Surface dressing of the ground including removing vegetation and in-equalities not exceeding 15 cm deep and disposal of rubbish, lead up to 50 m and lift up to 1.5 m. All kinds of soil (DAR 2018 Hort - 2.28.1) based	Sqm	2250.00	11.70
2	Supplying & stacking of selection NO.1 Doob grass at site fresh & free from weeds having proper roots in green including loading, unloading, carriage and all taxes paid etc. and as per direction of officer in charge. DSR 2018 Horticulture and landscaping SI No. 2.35	Sqm	126.00	38.90
3	Grassing with selection No.-1 including watering and maintenance of the lawn for 60 days or more till the grass forms a thick lawn, free from weeds and fit for mowing including supplying good earth, if needed (the grass and earth shall be paid for separately). DSR 2018 Horti - SI No. 2.10	Sqm	126.00	8.50
4	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), excavated soil and disposal of surplus excavated soil as directed within a lead of 50 m including dressing of sides and ramming of bottoms, lift upto 1.5 m including getting out the all kind of soil. DSR 2023/2.8.1	Cum	12.00	205.62
5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering. All work upto plinth level. 1:4:8 (1 Cement : 4 Coarse sand (zone-III) : 8 graded stone aggregate 40 mm (nominal size). DSR 2023/4.1.8	Cum	0.50	5381.13
6	Brick work with common burnt clay (non modular) bricks of class-150 in foundation and plinth in: Cement mortar 1:4 (1cement:4 Coarse sand). DSR 2023/6.1.1	Cum	0.65	5822.47
7	12 mm cement plaster of mix: 1:4 (1 Cement : 4 Coarse sand). DSR 2023/13.4.1	Sqm	3.40	282.28
8	Providing and fixing angle iron frames for doors, windows and ventilators of mild steel angle sections of size 35x35x5mm, joints mitres and welded by angle iron 35x35x5 mm or 35x5 mm flat pieces to the existing T-iron frame or to the wall with dash fastener, including fixing of necessary butt hinges and screws and applying a priming coat of approved steel primer, all complete as per direction of Engineer in charge. DSR 2023/10.31	Kg	393.00	103.08
9	Providing and laying in position ready mixed or site batched design mix cement concrete for plain cement concrete work, using coarse aggregate and fine aggregate derived from natural sources, Portland Pozzolana/ Ordinary Portland/ Portland slag cement, admixtures in recommended proportions as per IS : 9103 to accelerate/retard setting of concrete : All works upto plinth level : Concrete of M15 grade with minimum cement content of 240 Kg/cum. DSR 2023/4.20.1.2	Cum	3.00	7098.65

**TENDER DOCUMENT No.-06 (S. No-06)****लखनऊ विकास प्राधिकरण**

10	Supply and Fixing of Green Net for covering of Nursery. Sanctioned rate	Sqm	1170.00	85.00
11	Supply & Stacking of 1.25 inch Garden Rubber pipe etc all complete as per directed by the officer in charge. Sanction Rate.	Mtr	60.00	65.00
12	Providing and fixing G.I. chain link fabric fencing of required width in mesh size 50x50 mm including strengthening with 2 mm dia wire or nuts, bolts and washers as required complete as per the direction of Engineer-in-charge : Made of G.I. wire of dia 4 mm. DSR 2023/16.70.1	Sqm	180.00	804.01
13	Providing and Displaying Dianthus in different colour well developed with fresh & healthy foliage 30 cm ht., in full bloom with stacking in 25 cm Earthen Pot/Plastic Pot and as per direction of the officer-in-charge. (DAR 2018 Hort - 4.29) based	Nos	100.00	43.50
14	Providing and Displaying Petunia hybrid different colour single well developed in full bloom in 20 cm Earthen/Plastic Pot and as per direction of the officer-in-charge. (DAR 2018 Hort - 4.49) based	Nos	100.00	34.50
15	Providing and Displaying Dahlia double kenya variety in different colour well developed with 3 to 4 flowers in half bloom, good foliage stacked with Green painted Bamboo sticks, 45 to 60 cm height in 25 cm Earthen pot/Plastic Pot and as per direction of the officer-in-charge. (DAR 2018 Hort - 4.24) based	Nos	50.00	69.00
16	Providing and Displaying Marigold(Tagetes) inca hybrid different colour having 30 cm and above ht., with 6 to 8 flowers in bloom & blooming condition, well developed pot should be fully covered with fresh and healthy, foliage and flowers in 20 cm Earthen Pot/Plastic Pot and as per direction of the officer-in-charge. (DAR 2018 Hort - 4.40) based	Nos	50.00	51.50
17	Engagement of Unskilled labour. PWD SOR 2020-21/Chapter Labour Rates	Nos	14.00	357.50
Boring				
18	Boaring/ drilling bore well of required dia for casing/ strainer pipe, by suitable method prescribed in IS : 2800 part I, including collecting sample from different starta, preparing and submitting equipments, tools, plants & machineries required for the job, all complete as per direction of Engineer In charge, up to 90 meter depth below ground level. All type of soil (DAR 16 23.1.1 based) Sanction Rate			
a	0-15 m BGL	Rmt	15.00	160.00
b	15-30 m BGL	Rmt	15.00	170.00
c	30-65 m BGL	Rmt	35.00	200.00
19	Supply, assembling, lowering and fixing in vertical position in bore well unplasticized PVC medium well casing (CM) pipe of required dia conforming to IS: 12818 including required hire and labour charges, fittings & accessories etc. all complete for all depths as per direction of Engineer in charge. 100 mm nominal size dia PWD SOR 2020-21/DAR No. 23.3.1	Rmt	40.00	517.00

**TENDER DOCUMENT No.-06 (S. No-06)****लखनऊ विकास प्राधिकरण**

20	Supply, assembling, lowering and fixing in vertical position in bore well unplasticized PVC medium well screen (RMS) pipes with ribs, conforming to IS: 12818 including required hire and labour charges, fittings & accessories etc. all complete for all depths as per direction of Engineer in charge. 100 mm nominal size dia PWD SOR 2020-21/DAR No. 23.4.1	Rmt	16.00	561.00
21	Providing and fixing suitable size threaded mild steel cap or spot welded plate to the top of bore well housing/casing pipe, removable as per requirement, all complete for bore well of: 100 mm dia. PWD SOR 2020-21/DAR No. 23.13.1	Nos	1.00	164.00
22	Providing and fixing chlorinated Polyvinyl Chloride (CPVC) pipes having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings this includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in charge. 40 mm nominal outer dia pipes. PWD SOR 2020-21/DAR No. 18.9.5	Rmt	56.00	371.00
23	Providing & Fixing M.S. clamp of required dia to the top of casing/ housing pipe of tube well as per IS 2800 part - 1 including necessary bolts & nuts of required size complete. 100 mm clamp. PWD SOR 2020-21/DAR No. 23.14.1	Nos	1.00	1140.00
24	Gravel packing in tube well construction in accordance with IS: 4097 including providing gravel fine/ medium/ coarse in required grading & sizes as per actual requirement all complete as per direction of Engineer-in-charge. PWD SOR 2020-21/DAR No. 23.8	Cum	0.49	1218.00
25	Supply/ erection of 2 HP KSB/ Crompton or equalent submersible pump with motor including 15 sqm 3 core cable, (approx 45 meter length) including cost of steel rope & panel. Sanction Rate	Nos	1.00	20150.00

J.E.**A.E.**

I/we here by offer to execute the above work on%
above/below (in figures)above/below (in words).

Signature of Contractor**Address. :****Phone/Mobile No.:**