



लखनऊ विकास प्राधिकरण निविदा प्रपत्र

कार्य का नाम :- प्राधिकरण कार्यालय भवन गोमती नगर में मुख्य अभियन्ता कार्यालय कक्ष में फाल्स सीलिंग एवं ए0सी0 लगाने का कार्य।

कार्य का नाम	व्ययानुमान धनांक(रु0)	प्रतिभूति धनराशि (रु0)	समय	श्रेणी	निविदा मूल्य रु0
प्राधिकरण कार्यालय भवन गोमती नगर में मुख्य अभियन्ता कार्यालय कक्ष में फाल्स सीलिंग एवं ए0सी0 लगाने जाने का कार्य।	8,39,156.45 जी0एस0टी0 अतिरिक्त	42000.00	01 माह	“क” श्रेणी विद्युत लाइसेंस	767.00

- निविदा प्रपत्र निविदा सूचना में दी गई अवधि में वेबसाइट '<http://www.jdaonline.in>' से डाउन-लोड किये जायेंगे तथा पूर्ण रूप से भरे हुए एवं हस्ताक्षरित निविदाएं सीलबन्ध लिफाफे में निविदा सूचना में अंकित तिथियों को निर्धारित स्थान-आयुक्त, लखनऊ मण्डल, लखनऊ के नजारत कक्ष, जिलाधिकारी, लखनऊ कार्यालय के कलेक्ट्रेट स्थित कक्ष संख्या-25 तथा प्राधिकरण के नवीन भवन, गोमती नगर लखनऊ में रखे निविदा बाक्स में डाले जा सकेंगे।
- निविदा के साथ दी जाने वाली प्रतिभूति की धनराशि, कार्य पूर्ण करने हेतु निर्धारित समय, कार्य की श्रेणी व अन्य शर्तें एवं विवरण निविदा सूचना में अंकित शर्तों, विवरण एवं 'नोट' के अनुसार लागू होगी। निविदा सूचना निविदा प्रपत्र का एक अंश है।
- समस्त निविदाओं हेतु प्रतिभूति की धनराशि अधिशासी अभियन्ता, लखनऊ विकास प्राधिकरण को न्यस्त एन0एस0सी0/एफ0डी0आर0/एन0एस0एस0 के रूप में जमा करना होगा। यदि किसी निविदा के साथ उक्त प्रतिभूति धनराशि जमा नहीं होगी तो ऐसी स्थिति में निविदायें खोलते ही पुनः सील कर दी जाएंगी।
- ठेकेदारों के चालित देयको से 10 प्रतिशत उस समय तक काटा जाएगा जब तक कि बकाया 5 प्रतिशत जमानत का धन प्राप्त नहीं हो जाता है वह 5 प्रतिशत अन्तिम देयक में ठेकेदार को दे दिया जायेगा तथा 5 प्रतिशत कार्य सन्तोषजनक होने के बाद 12 माह बाद अनुरक्षण अवधि समाप्त होने के बाद वापस किया जायेगा।
- किसी भी अथवा समस्त निविदाओं को अस्वीकृत कर देने का अधिकार सुरक्षित रहेगा इस सम्बन्ध में किसी भी व्यक्ति तथा व्यक्तियों द्वारा निविदा के अस्वीकृत होने के कारण को पूछा नहीं जा सकता है।
- निविदा की स्वीकृति प्राप्त करने वाले ठेकेदार को स्वीकृत पत्र प्रमाण लेख पर हस्ताक्षर करने होंगे।
- किसी भी निविदा पर विचार नहीं किया जायेगा जब तक कि उसके साथ अग्रिम धनराशि जमा करने की रसीद अथवा निविदा सूचना के अनुसार अग्रिम धनराशि संलग्न न होगी।
- निविदा की दर तथा जोड़ को शब्दों तथा अंकों में स्पष्ट रूप से भरा जायें तथा कोई भी कटिंग व ओवर राईटिंग न की जायेगी अन्यथा निविदा अस्वीकृत कर दी जायेगी।
- यदि निविदा की स्वीकृति प्राप्त करने वाले ठेकेदार 15 दिन के अन्दर स्पष्ट रूप से कान्ट्रेक्ट पर हस्ताक्षर नहीं करेगा तो निविदा के साथ जमा किया हुआ धन जब्त कर लिया जायेगा तथा निविदा की स्वीकृति वापस कर ली जायेगी।
- ठेकेदार अपनी निविदा में दर उसी प्रकार से भरेगा जिस प्रकार से निविदा पत्र में मांगी गयी हों।
- निविदा देने की तिथि से 50,000 रु0 से कम की निविदा 4 माह तक वैध रहेगी तथा इसके ऊपर के धनराशि की निविदा 6 माह तक वैध रहेगी।



TENDER DOCUMENT NO.- 01/E-NIVIDA/CE/2023-24(21)

12. जो निविदा पता ठेकेदार का निविदा में मिलेगा वही पता मान्य होगा और इस पते पर भेजी गई डाक यदि डाकखाने से किसी कारण से वितरित न होकर वापस हो जाती है तो समझा जायेगा कि ठेकेदार द्वारा स्वीकार कर ली गई है।
13. प्रत्येक निविदा केसाथ अलग से अग्रिम धनराशि होनी चाहिए, दूसरे निविदा के साथ लगी अग्रिम धनराशि मान्यन होगी।
14. पुरानी सिक्कोरिटी या अग्रिम धनराशि जो विभाग द्वारा वापस की जाती है उसको अग्रिम धन के रूप में इंगित किया जायेगा तो मान्य न होगी।
15. प्रत्येक कार्य के निविदा प्रपत्र की मूल प्रति विभाग में सुरक्षित रखी गयी है। प्राप्त निविदाओं में किसी भी प्रकार की भिन्नता स्वीकार योग्य नहीं होगी एवं विवाद की स्थिति में मूल प्रति ही अंकित होगी।
16. प्रत्येक कार्य की निविदा के लिफाफे पर कार्य का नाम स्पष्ट रूप से अंकित होगी।
17. सभी साधारण एवं विशेष शर्तें/नियमों का पालन न होने पर निविदा मान्य न होगी और ठेकेदार को डिबार कर दिया जायेगा एवं ब्लैक लिस्ट भी किया जा सकता है।

हस्ता०
प्रमाणित ---
प्रधान लिपिक {अभि० विभाग}

ठेकेदार के हस्ताक्षर
तथा पता :

हस्ता०
अधिशायी अभियन्ता
लखनऊ विकास प्राधिकरण



कार्यालय:
अधिकासी अभियन्ता (वि०/यॉ०)
लखनऊ विकास प्राधिकरण,
लखनऊ।

पत्रांक : 01 / ई-निविदा / मु०अ० / 2024-25,

दिनांक : 07.06.2024

निविदा सूचना

लखनऊ विकास प्राधिकरण द्वारा विभाग में पंजीकृत ठेकेदारों से निम्नलिखित कार्यो हेतु मुद्रांकित निविदाएं आमंत्रित की जाती है। कार्य के निविदा प्रपत्र वेबसाइट "http:\\ www.ldaonline.in "से डाउन लोड किये जा सकेंगे एवं, आयुक्त लखनऊ मण्डल कार्यालय के नजारत कक्ष, जिलाधिकारी, लखनऊ के कलेक्ट्रेट स्थित कार्यालय के कक्ष संख्या 25 तथा प्राधिकरण के नवीन भवन स्थित निविदा बाक्स में स्तम्भ (8) में अंकित तिथियों में डाले जा सकेंगे अथवा रजिस्टर्ड डाक से अपराह्न 3.00 बजे तक भेजे जा सकते हैं, परन्तु निर्धारित समय के पश्चात् प्राप्त निविदाओं पर विचार नहीं किया जाएगा। प्राप्त निविदाएं, निविदा डालने की अंतिम तिथि को अपराह्न 4.00 बजे ठेकेदारों अथवा उनके अधिकृत प्रतिनिधियों (यदि उपस्थित हुए) के समक्ष प्राधिकरण भवन स्थित अधिकासी अभियन्ता (वि०/यॉ०) जोन-6 के कार्यालय कक्ष में खोली जाएगी।

क्र० सं०	कार्य का नाम	व्ययानुमान धनराशि (रु०)	प्रतिभूति धनराशि (रु०)	कार्य पूर्ण करने की अवधि	पंजीकृत श्रेणी	निविदा मूल्य (रु०)	निविदा डालने की अवधि
1	2	3	4	5	6	7	8
1.	प्राधिकरण कार्यालय भवन गोमती नगर में मुख्य अभियन्ता कार्यालय कक्ष में फाल्स सीलिंग एवं ए०सी० लगाने का कार्य।	8,39,156.45 जी०एस०टी० अतिरिक्त	42000.00	01 माह	निर्देशक, विद्युत निदेशालय उ०प्र० शासन द्वारा प्रदत्त 'क' श्रेणी विद्युत लाइसेंस धारक एवं क्षेणी-डी (वि०/यॉ०)/सिगल बिड	767.00	18.06.2024 अपराह्न 3.00 बजे तक

नोट:-

- समस्त निविदाओं हेतु प्रतिभूति की धनराशि अधिकासी अभियन्ता, लखनऊ विकास प्राधिकरण को न्यस्त एन.एस.सी./ एफ.डी.आर./ एन.एस.एस. के रूप में जमा करना होगा यदि किसी निविदा के साथ उक्त प्रतिभूति धनराशि जमा नहीं होगी तो ऐसी निविदाओं को खोलते ही पुनः सील कर दिया जाएगा।
- निविदा मूल्य नगद/ बैंक ड्राफ्ट के रूप में सचिव, लखनऊ विकास प्राधिकरण के पक्ष में देय होगी, जो वापस नहीं होगी।
- निविदा के साथ पंजीकरण के नवीनीकरण की रशीद की छायाप्रति संलग्न करना अनिवार्य होगा।
- कार्यालय अवकाश की दशा में अगले कार्य दिवस तक निविदा वेबसाइट से लोड की जा सकेगी/ डाली जा सकेगी। अगले कार्यदिवस को खोली जायेगी।
- किसी भी निविदा को स्वीकृत अथवा अस्वीकृत करने का पूर्ण अधिकार उपाध्यक्ष, लखनऊ विकास प्राधिकरण में निहित होगा।
- अन्य जानकारी अधोहस्ताक्षरी के कार्यालय से ज्ञात की जा सकती है।

(मनोज कुमार सागर)
अधिकासी अभियन्ता



LUCKNOW DEVELOPMENT AUTHORITY

कार्य का नाम :- प्राधिकरण कार्यालय भवन गोमती नगर में मुख्य अभियन्ता कार्यालय कक्ष में फाल्स सीलिंग एवं ए0सी0 लगाने का कार्य।

SPECIFICATION

- Method of tendering 1. The contractor must fill in ink schedule 'G' and the Supplementary schedule 'H' item by item in the several columns and must write in words well as in figures the rates per unit of measurement of each item. In column provided in the schedule 'G' and 'H' Each page of both schedules must also be signed by the contractor or duly accredited agent acting on his behalf it is strictly forbidden to modify or change the arithmetical totals of any or all the tenders items by a percentage deduction or increase and tender is received will be liable to be rejected.
- Terms of Tender 2. Firm prices in rupees and paise shall be quoted for each item in the schedule 'G' and 'H' and tender shall remain good and open for acceptance for a period of four calendar month from the date of opening of tender.
- Water Supply 3. The contractor shall make his own arrangements in regard to water supply required for execution and test of the works as well as for drinking water for his own work people and he shall defray all charges in this connection and include in his rates a sufficient amount to allow for this. In case the contractors takes water from Corporation taps, charges at their of 2% of the cost of the work done shall be deducted from his bill.
- Standard Detailed Specification 4. All works executed or materials supplied under this contract unless otherwise specific in these specification shall comply with the description set out in Public Works Department detail or the Indian standard specification or L. S. G. E. D. Detailed specifications in for as they are applicable shall be deemed to be incorporated in this contract.
- Small and Scattered



Works

5. The contractor may be required to carry out works in small quantities repairs or minor alterations to existing drains, pipe lines. Payments, locking existing mains and other miscellaneous purposes in connection with work. He shall be paid separately for work so carried out the rate tendered in schedule 'G' and 'H' for such items i.e. for boulder masonry brick work concrete excavation plaster & pointing etc, and no claim of any extra payments on ground of small work or due to its being of scattered nature shall be entertained.

Extra Rate

6. Any new rates not given in the tender but given in the current P. W. D. /L. S. G. E. D., schedule of rates shall be paid for according to rates on percentage (above or below) the current P.W. D./L. S. G. E.D. schedule of rates calculated on the accepted tender over the estimated cost of the work or as decided by the Adhishasi Abhiyanta which ever is less.

7. Any new rates not given in Mahapaliks schedule of rates shall be decided by the Adhishasi Abhiyanta and decision will be final.

Brick Wrok

8. All brick works shall be paid according to brick size i.e. the thickness of walls shall half brick 4 ½" one brick 9" and 1 ½ brick 13 ½" and so on and of slab and lintels etc. 3", 4 ½", 6" and so on.



LUCKNOW DEVELOPMENT AUTHORITY

कार्य का नाम: प्राधिकरण कार्यालय भवन गोमती नगर में मुख्य अभियन्ता कार्यालय कक्ष में फाल्स सीलिंग एवं ए0सी0 लगाने का कार्य।

SCHEDULE 'A'

The work is to be done in connection with.....

The site of work can be ascertained from the Assistant Engineer (Project Lucknow Development Authority, Lucknow).

The tenders are advised to inspect the site of the work6 Month.....

Before tendering the rates so that they may fully acquaint themselves with the nature of the work to be done, the means of communication and availability of materials and water required for the work.

The contractor must complete the work in accordance with the specification and to the entire satisfaction of the Engineer-in-charge with the specified period.

SCHEDULE 'B'

The drawings regarding this, this work can be seen in the office of Adhishashi Abhiyanta Lucknow Development Authority on any working day from 10 A.M. to 5 P.M.

SCHEDULE 'C'

Nil

SCHEDULE 'D'

The following samples be submitted by the contractor within 10 days of the receipt of orders to start the work and subsequent supplies shall not be inferior to the samples approved.

1-	Bricks	10 Nos.	Surkhi	1Cft.
2-	Sand coarse	1 Cft.	Brick ballast	1 Cft.
3-	Local Sand	1 Cft.	Any other sample	Desired by the Engineer
4-	Hard stone grit	1 Cft.		

Materials specified by the Engineer from time to time and brought on the site of work shall occasionally be tested by the Engineer at the cost of the Contractor. The material rejected shall be removed by the contractor within 24 hours, failing which the rejected materials shall be removed or disposed of by the Lucknow Development Authority at the cost of the contractor.



SCHEDULE 'I'

- 1 All materials supplied by the contractor brought on the site shall be tested by the Engineer-in-charge frequently to check up if they confirm the specification of P.W.D.
- 2 All the rates as may be necessary shall performed at the contractor's expenses and will have to make all necessary arrangement for conducting them and when called upon on to do so to the satisfaction of the Engineer.

SCHEDULE 'F'

All works specified herein shall be completed in all respect to the entire satisfaction of the Engineer-in-charge and handed over to him or any persons nominated by to take over within a period ofONE.....months from the date of receipt written order to commence the work.

The contractor's responsibility shall, however, not & until the maintenance period of one year or one rainy season with which ever is more from the date of completion is over is any defect is notified at the contractor's cost.

Individual portions of the work may be brought into use of the Lucknow Development Authority as each section is completed but maintenance period of one year or one rainy season which ever is more shall be finally counted from the date of entire work under the contract is finally completed and handed over.



TENDER FORM

Schedule –G

1. The tenderers are advised to read the additional special condition and specifications, instruction and important notes before filling the rates.
2. While tendering the contractor should visit the site of work and investigate the nature of the soil.
3. Quantities of various items of work are given in this schedule are approximate. The payment may be made on the actual measurement of work done.
4. Supply of all materiel of various item of work are given in this schedule 'I'
5. The responsibility for upkeep and watch ward of work will be the contractor up to explore of the maintenance period.

Name of Work: प्राधिकरण कार्यालय भवन गोमती नगर में मुख्य अभियन्ता कार्यालय कक्ष में फाल्स सीलिंग एवं ए0सी0 लगाने का कार्य।

S.No.	Items	Quantity	Rate per Unit
1-	False Ceiling 3: (DAR 26.21. (PSR Camp Office) Providing and fixing false ceiling at all heights with integral densified calcium silicate reinforced with fibre and natural filler false ceiling tiles of Size 595x595 mm of approved texture, design and patterns having NRC (Noise Reduction coefficient) of 0.50 (minimum) as per 15 8225:1987, Light reflectance of 85% (minimum) Nen combustible as per B5:476 (part-4), fire performance as per BS 476 (part 647) humidity resistance of 100%, thermal conductivity < 0.043 W/m K as per ASTM 518:1991, in true horizontal level suspended on interlocking metal powder coated T-Grid of hot dipped galvanised iron section of 0.40 mm thick on Silhouette profile rotary stiched double webbed white with 6mm reveal profile (white/black).comprising of main-T runners of size 15x42mm of length 3000 mm, cross-T of size 15x42 mm of length 1200 mm and secondary intermediate cress T of size 15x42 mm of length 600mm to form grid module of size 600 x 600 mm, süsuspended from ceiling using galvanised mild steel items (galvanizing 10 grams per sqm) Le. 50 mm long, 11 mm outer diameter M-6 dash fasteners, 6 mm dia fully threaded hanger rod upto 1000 mm length and L-shape level adjuster of size 85x25x2 mm. Galvanised iron perimeter wall angle of size 22x19x0.40 mm of length 3000 mm to be fixed on periphery wall/partition with the help of plastic rawl plugs at 450 mm center to center and 40mm long dry wall SS screws The work shall be carried out as per specifications, drawing and as per directions of the Engineer-in-Charge. With 15 mm thick integral densified micro edge light weight calcium	50 sqm	2750.00
2	False Ceiling 2: Providing & fixing of Gypsum False Ceiling with Murga jali & support of sal wood frame including Gypsum and required boards with putty, penning & required plaster of paris given a smooth surface induding T&P etc all complete in directin of engineer in charge.	17 Nos.	2152.80
3	VRV Variable Refrigerant Flow System Supply of 100% Inverter based variable refrigerant flow modular type air-conditioning system of R410A having proven single inverter driven scroll Compressor technology		
4	Outdoor Units (Heat Pump type) 08 HP	1 Nos.	251000.00
	Indoor Units		
5	Cassette type Unit : 3.33 TR	2 Nos.	43460.00
	Individual Controllers		
6	Carded Remote Controls	2 Nos.	4100.00
7	T-Joints Providing & fixing of T-Joints as per site requirement	2 Nos.	4850.00
	Low Side work		
8	Installation charges of outdoor units: Lifiging, sifting, positioning of outdoor units	1 Nos.	12500.00
9	Installation charges of outdoor units: Lifiging, sifting, positioning of indoor units	2 Nos.	4000.00
10	Additional Gas charging Topping R410A gas as per site requirement.	10 Nos.	1050.00



TENDER DOCUMENT NO.- 01/E-NIVIDA/CE/2023-24(21)

11	Commissioning charges of VRF System	10 Nos.	450.00
	Refrigerant Piping & Insulation Supply & installation charges for interconnecting refrigerant pipe work suitable for refrigerant flow.		
I	41.3 MM O.D.		
li	34.4 MM O.D.		
lii	28.6 mm O.D.	17.50 RMT	1800.00
Iv	22.2 mm O.D.	15.00 RMT	1650.00
V	19.1 MM O.D.	17.50 RMT	1550.00
Vi	15.9 MM O.D.	22.50 RMT	1450.00
Vii	12.7 MM O.D.	20.00 RMT	1350.00
Viii	9.5 MM O.D.	15.00 RMT	1150.00
Ix	6.4 MM O.D.	20.00 RMT	950.00
12	Drain Piping Providing and fixing rigid PVC piping complete with fittings, supports as per specifications and duly insulated with 6 mm thick closed cell, nitrite rubber insulation. 32 mm dia	50 RMT	250.00
13	Transmission wiring Providing & fixing control cum transmission wiring of 2 core x 1.0 Sqmm copper in suitable conduits between indoor and outdoor units.	111 RMT	180.00
14	Controller wiring Providing & fixing control cum transmission wiring of 2 core x 1.0 Sqmm copper in suitable conduits between indoor and outdoor units.	30 RMT	180.00
15	Supply & Laying of MS Slotted Angle for pipes and cables horizontally and vertically along with threaded rod, nut bolt, saddle, tie etc.	15 RMT	130.00
16	Distempering with 1st quality acrylic distemper (ready mixed) having VOC content less than 50 gram/litre, of approved manufacturer and of required shade and colour all complete to achieve even shade and colour : New work (two or more coats) over and including water thinnable priming coat with cement primer having VOC content less than 50 gram/litre. DSR-2023/13.41.1	69 sqm	146.65
17	Supply and fixing of 36 watt indoor recess mounting LED square fitting for arm strong ceiling having powder coated die cast aluminium housing body with extended heat sink and diffuser of special polycarbonate material and driver set complete in all respect as per PWD Schedule 2018 SI No. 1406 CAT AAA\	8 Nos.	4880.00
	GST EXTRA 18%		

Prepared by J.E

Checked by A.E

I/We hereby offer to execute the above work on _____ Above \ below.

Signature of the contractor & Address: