



**TENDER DOCUMENT No.-21\_10**  
**लखनऊ विकास प्राधिकरण**  
**निविदा-प्रपत्र**

1. कार्य का नाम: सी0जी0 सिटी योजना स्थित पराग चौराहे से कैसर संस्थान एवं मेडिकल विश्वविद्यालय तक हाईमास्ट, स्ट्रीट लाईट एवं पैनल के सुदृढीकरण का कार्य।

2.

कार्य का नाम	बी0ओ0क्यू0 धनांक (₹0)	प्रतिभूति धनराशि (₹0)	समय	श्रेणी	निविदा मूल्य (₹0)
सी0जी0 सिटी योजना स्थित पराग चौराहे से कैसर संस्थान एवं मेडिकल विश्वविद्यालय तक हाईमास्ट, स्ट्रीट लाईट एवं पैनल के सुदृढीकरण का कार्य।	8,21,761.20	41,100.00	01 माह	निदेशक, विद्युत सुरक्षा निदेशालय, उ.उ. शासन द्वारा प्रदत्त 'क'-श्रेणी विद्युत लाइसेंस धारक एवं श्रेणी-डी (वि0/यां0/सिंगल बिड	650.00 +18% GST

3. निविदा प्रपत्र निविदा सूचना में दी गई अवधि में वेबसाइट '<http://www.ldaonline.in>' से डाउन-लोड किये जायेंगे तथा पूर्ण रूप से भरे हुए एवं हस्ताक्षरित निविदाएं सीलबन्ध लिफाफे में निविदा सूचना में अंकित तिथियों को मुख्य अभियन्ता, लखनऊ विकास प्राधिकरण गोमती नगर लखनऊ में रखे निविदा बाक्स में डाले जा सकेंगे। निविदा के साथ दी जाने वाली प्रतिभूति की धनराशि, कार्य पूर्ण करने हेतु निर्धारित समय, कार्य की श्रेणी व अन्य शर्तें एवं विवरण निविदा सूचना में अंकित शर्तों, विवरण एवं 'नोट' के अनुसार लागू होगी। निविदा सूचना निविदा प्रपत्र का एक अंश है।
4. समस्त निविदाओं हेतु प्रतिभूति की धनराशि एन0एस0सी0/एफ0डी0आर0/एन0एस0एस0 के रूप में, जो अधिशासी अभियन्ता, लखनऊ विकास प्राधिकरण के पक्ष में बंधक होगी। निविदा के साथ संलग्न करनी होगी। यदि किसी निविदादाता द्वारा निविदा प्रपत्र के साथ उक्त प्रतिभूति धनराशि एवं निविदा प्रपत्र शुल्क का साक्ष्य संलग्न नहीं पायी जायेगी, तो ऐसी स्थिति में प्राप्त निविदा मान्य नहीं होगी एवं प्राप्त निविदा पर विचार नहीं किया जायेगा।
5. ठेकेदारों के चालित देयको से 10 प्रतिशत जमानत धनराशि उस समय तक काटा जाएगा जब तक कि बकाया 5 प्रतिशत जमानत का धन प्राप्त नहीं हो जाता है वह 5 प्रतिशत अन्तिम देयक में ठेकेदार को दे दिया जायेगा तथा 5 प्रतिशत कार्य सन्तोषजनक होने के बाद 12 माह बाद अनुक्षण अवधि समाप्त होने के बाद वापस किया जायेगा। अस्थायी कार्य हेतु कार्य सन्तोषजनक पूर्ण होने एवं अन्तिम भुगतान के पश्चात् जमानत धनराशि वापिस कर दी जायेगी।
6. किसी भी निविदा को स्वीकृत अथवा अस्वीकृत करने का अधिकार उपाध्यक्ष, ल0वि0प्रा0 में निहित होगा। इस सम्बन्ध में किसी भी व्यक्ति तथा व्यक्तियों द्वारा निविदा के अस्वीकृत होने के कारण को पूछा नहीं जा सकता है।
7. निविदा की स्वीकृति उपरान्त सम्बन्धित ठेकेदार को अनुबंध निष्पादन हेतु नियमानुसार आवश्यक प्रपत्र उपलब्ध कराते हुए प्राधिकरण एवं फर्म के बीच निष्पादित अनुबंध प्रपत्र पर हस्ताक्षर करने होंगे।
8. निविदा की दर तथा जोड़ को शब्दों तथा अंकों में स्पष्ट रूप से भरा जायें तथा कोई भी कटिंग व ओवर राईटिंग न की जायेगी अन्यथा निविदा अस्वीकृत कर दी जायेगी।
9. निविदा की स्वीकृति के उपरान्त सम्बन्धित फर्म को निर्धारित अवधि के अन्तर्गत अनुबंध निष्पादित कराना अनिवार्य होगा।
10. ठेकेदार अपनी निविदा में दर उसी प्रकार से भरेगा जिस प्रकार से निविदा पत्र में मांगी गयी हों।
11. निविदा की दरे निविदा प्राप्त होने की तिथि 90 दिनों तक वैध रहेगी।
12. निविदा की मदों की मात्राओं में घटत एवं बढ़त हो सकती हैं, जो निविदादाता को मान्य होगी।
13. जो निविदा पता ठेकेदार का निविदा में मिलेगा वही पता मान्य होगा और इस पते पर भेजी गई डाक यदि डाकखाने से किसी कारण से वितरित न होकर वापस हो जाती है तो समझा जायेगा कि ठेकेदार द्वारा स्वीकार कर ली गई है।
14. प्रत्येक निविदा के साथ अलग-अलग प्रतिभूति धनराशि संलग्न करनी होगी।
15. प्रत्येक कार्य के निविदा प्रपत्र की मूल प्रति विभाग में सुरक्षित रखी गयी है। प्राप्त निविदाओं में किसी भी प्रकार की भिन्नता स्वीकार योग्य नहीं होगी एवं विवाद की स्थिति में मूल प्रति ही अंकित होगी।
16. प्रत्येक कार्य की निविदा के लिफाफे पर कार्य का नाम एवं निविदादाता का नाम स्पष्ट रूप से अंकित होगा।
17. सभी साधारण एवं विशेष शर्तें/नियमों का पालन न होने पर निविदा मान्य न होगी और ठेकेदार को डिबार कर दिया जायेगा एवं ब्लैक लिस्ट भी किया जा सकता है।
18. निविदादाता द्वारा उ0प्र0 लोक निर्माण विभाग-12 के शासनादेश सं0-622/23-12-2012-2 आडिट/08 टी0सी0-2 दिनांक 08.06.2012 के अनुसार आगणित दरों से 10 प्रतिशत से अधिक निम्न दर दिये जाने पर 10 प्रतिशत निम्न तक 0.50 प्रतिशत प्रति 1.0 प्रतिशत कम दर पर तथा 10 प्रतिशत से अधिक निम्न दर पर 1.0 प्रतिशत प्रति 1.0 प्रतिशत कम दर पर अतिरिक्त सिक्वोरिटी/परफॉरमेन्स गारन्टी की धनराशि अनुबंध के समय एन0एस0सी0/एफ0डी0आर0/एन0एस0एस0 के रूप में, जो अधिशासी अभियन्ता, लखनऊ विकास प्राधिकरण के पक्ष में बंधक होगी, उपलब्ध करानी होगी।

हस्ता0  
प्रमाणित —  
प्रधान लिपिक {अभि0 विभाग}

ठेकेदार के हस्ताक्षर  
तथा पता :

हस्ता0  
अधिशासी अभियन्ता (वि0/यां0)  
लखनऊ विकास प्राधिकरण



**TENDER DOCUMENT No.-21\_10**  
**लखनऊ विकास प्राधिकरण**

**कार्यालय : मुख्य अभियन्ता**  
लखनऊ विकास प्राधिकरण,  
प्राधिकरण भवन, गोमती नगर,  
लखनऊ।

संख्या : 21/निविदा/मु0अ0/2024-25

दिनांक : 19/07/2024

-: निविदा सूचना :-

लखनऊ विकास प्राधिकरण में पंजीकृत ठेकेदारों से निम्नलिखित कार्यो हेतु मुद्रांकित निविदाएं आमंत्रित की जाती हैं। कार्य के निविदा प्रपत्र वेबसाइट "http://www.ldaonline.in" से डाउनलोड किये जा सकेंगे एवं आयुक्त, लखनऊ मण्डल कार्यालय के नजारत कक्ष, जिलाधिकारी, लखनऊ के कलेक्ट्रेट स्थित कार्यालय के कक्ष संख्या-25 तथा प्राधिकरण के नवीन भवन स्थित निविदा बाक्स में स्तम्भ (8) में अंकित तिथियों में डाले जा सकेंगे अथवा रजिस्टर्ड डाक से अपराह्न 3:00 बजे तक भेजे जा सकते हैं, परन्तु निर्धारित समय के पश्चात् प्राप्त निविदाओं पर विचार नहीं किया जाएगा। प्राप्त निविदाएं, निविदा डालने की अंतिम तिथि को अपराह्न 4:00 बजे ठेकेदारों अथवा उनके अधिकृत प्रतिनिधियों (यदि उपस्थित हुए) के समक्ष प्राधिकरण के नवीन भवन में अधिशासी अभियन्ता कार्यालय कक्ष में खोली जाएंगी।

क्रम सं०	कार्य का नाम	बी०ओ०क्यू० धनराशि (रु०)	प्रतिभूति धनराशि (रु०)	कार्य पूर्ण करने की अवधि	पंजीकृत श्रेणी	निविदा मूल्य (रु०)	निविदा डालने की अवधि
1	2	3	4	5	6	7	8
1.	सी०जी० सिटी योजना स्थित पराग चौराहे से कैंसर संस्थान एवं मेडिकल विश्वविद्यालय तक हाईमास्ट, स्ट्रीट लाईट एवं पैनल के सुदृढीकरण का कार्य।	8,21,761.20	41,100.00	01 माह	निदेशक, विद्युत सुरक्षा निदेशालय, उ. उ. शासन द्वारा प्रदत्त 'क'-श्रेणी विद्युत लाइसेंस धारक एवं श्रेणी-डी (वि०/या०/सिं गल बिड	650.00 +18% GST	20.07.2024 से 03.07.2024 अपराह्न 3:00 बजे तक

**नोट :**

- समस्त निविदाओं हेतु प्रतिभूति की धनराशि अधिशासी अभियन्ता, ल०वि०प्रा० को न्यस्त एन.एस.सी./एफ.डी. आर./एन.एस.एस. के रूप में जमा करना होगा। यदि किसी निविदा के साथ उक्त प्रतिभूति धनराशि जमा नहीं होगी, तो ऐसी निविदाएं खोलते ही पुनः सील कर दी जाएंगी।
- निविदा मूल्य नगद/बैंक ड्राफ्ट के रूप में सचिव, लखनऊ विकास प्राधिकरण के पक्ष में देय होगी, जो वापस नहीं होगी।
- निविदा के साथ पंजीकरण के नवीनीकरण की रसीद की छायाप्रति संलग्न करना अनिवार्य होगा।
- सड़क के कार्यो में बिटुमिन के प्रयोग की दशा में बिटुमिन की खरीद का प्रमाण पत्र कार्य के दौरान उपलब्ध कराना होगा। यदि कार्य हॉटमिक्स प्लाण्ट के माध्यम से कराया जाएगा तो बिटुमिन की खरीद का प्रमाण पत्र प्लाण्ट की ओर से दिया जाना अनिवार्य होगा।
- कार्यालय अवकाश की दशा में अगले कार्य दिवस तक निविदा वेबसाइट से लोड की जा सकेगी/डाली जा सकेगी/अगले कार्य दिवस को खोली जाएगी।
- किसी भी निविदा को स्वीकृत अथवा अस्वीकृत करने अथवा विभाजित करने का पूर्ण अधिकार उपाध्यक्ष, लखनऊ विकास प्राधिकरण में निहित होगा।
- अन्य जानकारी अधोहस्ताक्षरी के कार्यालय से ज्ञात की जा सकेगी।

**मुख्य अभियन्ता**



**TENDER DOCUMENT No.-21\_10**  
**लखनऊ विकास प्राधिकरण**  
**SCHEDULE 'A'**

The work is to be done in connection with.....

.....

The site of work can be ascertained from the Assistant Engineer (Project Lucknow Development Authority, Lucknow).

The tenders are advised to inspect the site of the work .....  
Before tendering the rates so that they may fully acquaint themselves with the nature of the work to be done, the means of communication and availability of materials and water required for the work.

The contractor must complete the work in accordance with the specification and to the entire satisfaction of the Engineer Incharge with the specified period.

**SCHEDULE 'B'**

The drawings regarding this, this work can be seen in the office of Adhishashi Abhiyanta Lucknow Development Authority on any working day from 10 A.M. to 5 P.M.

**SCHEDULE 'C'**

-- NIL --

**SCHEDULE 'D'**

The following samples be submitted by the contractor within 10 days of the receipt of orders to start the work and subsequent supplies shall not be inferior to the samples approved.

1. Bricks	10 Nos.	Surkhi	1 Cft.
2. Coarse Sand	1 Cft.	Brick ballast	1 Cft.
3. Local Sand	1 Cft.	Any other sample	Desired by the Engineer
4. Hard stone grit	1 Cft.		

Materials specified by the Engineer from time to time and brought on the site of work shall occasionally be tested by the Engineer at the cost of the Contractor. The material rejected shall be removed by the contractor within 24 hours, failing which the rejected materials shall be removed or disposed of by the Lucknow Development Authority at the cost of the contractor.



**TENDER DOCUMENT No.-21\_10**  
**लखनऊ विकास प्राधिकरण**  
**SCHEDULE 'I'**

1. All materials supplied by the contractor brought on the site shall be tested by the Engineer Incharge frequently to check up if they confirm the specification of P.W.D.
2. All the rates as may be necessary shall be performed at the contractor's expenses and will have to make all necessary arrangements for conducting them and when called upon to do so to the satisfaction of the Engineer.

**SCHEDULE 'F'**

All works specified herein shall be completed in all respects to the entire satisfaction of the Engineer Incharge and handed over to him or any persons nominated by him to take over within a period of .....months from the date of receipt of written order to commence the work.

The contractor's responsibility shall, however, not extend until the maintenance period of one year or one rainy season with whichever ever is more from the date of completion is over if any defect is notified at the contractor's cost.

Individual portions of the work may be brought into use by the Lucknow Development Authority as each section is completed but the maintenance period of one year or one rainy season whichever ever is more shall be finally counted from the date of entire work under the contract is finally completed and handed over.



**TENDER DOCUMENT No.-21\_10**  
**लखनऊ विकास प्राधिकरण**  
**SCHEDULE I**

The department will supply the following materials at the rate mentioned against each.

SI. No.	Name of the material	Rate	Place of issue	Remarks
1-	Nil		Nil	
2-	Nil		Nil	

**CONDITIONS**

1. The Engineer and subordinate incharge shall be free inspect the godown of Contractor at any time.
2. Every effort will be made by the L.D.A. for continuous supply of the above Material but the department dose not guarantee for the same and it will have to be arranged by the contractor without any claim. It should carefulled noted by the contractor that no compensation whatsoever shall be given to them for any interruption in the work for want of supply of material form the L.D.A. or any other case whatsoever.
3. Material issued to the contractor shall be carted by them to the site of work at his own cost.
4. Stores supplied by the department, if found damaged or missing shall be recovered at double the rate of issue. In case of materials supplied free of cast the deductions shall be made at double the book value of the material.
5. Any other material not easily available in the market at the time of construction but existing in the department store can be issued at the store issue rate plus 10% or market rate whichever is higher on the written request of the contractor.
6. The contractor will have to make his own arrangement for the all T.P. machinery and other equipment required to complete the work under his contract.

Contractor.....

Dated.....

Witness.....

Dated.....



**TENDER DOCUMENT No.-21\_10**  
**लखनऊ विकास प्राधिकरण**

**LUCKNOW DEVELOPMENT AUTHORITY LUCKNOW**

**SPECIAL CONDITIONS FOR WORK**

All the work shall be carried out as per detailed U.P.P.W.D., U.P. JAL NIGAM, U.P. POWER CORPORATION LTD., M.O.S.T. (Road Wing) specifications for road and bridge work (third revision 1995) as the case may be, latest circulars and instructions issued time to time as per instructions of Engineer-in-charge and other inspecting officers.

**EXTENT OF CONTRACT**

The Contract comprises construction and completion of the specified job and the provisions of all labour, materials, T&P etc. and transport, temporary works etc. whether of temporary or permanent in nature required for the construction, completion and maintenance of the work.

**INSPECTIONS OF THE SITE**

The tenderer (s) must inspect and examine the site of work and its surroundings and satisfy himself/themselves before submitting his/their tender. He/they has/have to make sure of the positions of quarries and availability of required material from quarries mentioned in the specifications, topography of the site availability of labour and material and other amenities before tendering. No claim for additional work or extra work due to any of the above will be allowed.

**ENTRIES IN TENDER**

All entries by the tenderer should be in one ink and one hand/on prescribed bill of quantity only. Eraseres and overwriting are not permissible. All corrections should be neatly written and signed by the tenderer. Rate should be written in figures as well as in words. In case there is any variation, lower rate shall be treated as Tender rate.

**CONDITIONAL/INCOMPLETE TENDER**

Conditional, incomplete, unsigned tenders will not be considered. Only those bidders who supply necessary proof/documents of possession of the required equipments in their bids should be considered as responsive for further evaluation.

**ADDRESS OF CONTRACTOR**

The contractor shall give his full permanent postal address. The postal receipt of the letters sent to him on this address shall be considered sufficient proof that they have been delivered to him.

**ACCEPTANCE OF TENDER**

The department shall have the right to accept or reject any or all the tenders or part thereof, without assigning any reason to contractor and no claim whatsoever shall be entertained on this account.



**TENDER DOCUMENT No.-21\_10**  
**लखनऊ विकास प्राधिकरण**

**SIGNING OF TENDER DOCUMENTS**

Contractor shall sign each page of tender documents before offering his tender and required stamp duty on the contract deed will be borne by the contractor.

**COPY OF CONTRACT**

On request, the Executive Engineer may furnish the contractor with a copy of the contract.

**TIME OF COMPLETION**

The time of completion as shown in this tender is for completion of the entire work.

**EMPLOYMENT OF LABOUR**

The contractor shall submit a daily report to the Engineer-in-charge regarding the total labour employed by him for the work and shall be bound to pay wages which shall not be less than the wages fixed under Minimum Wages Act.

**LINE AND LEVELS**

The contractor shall be solely responsible for setting out the works and for the correctness of the position, levels, dimensions and alignment according to the specification and shall provide all necessary assistance, instruments, pegs, sticks, poles and other materials, required for the purpose. The tender rates shall be deemed to include all this.

**PROGRAMME AND RETURNS TO BE FURNISHED**

As soon as practicable, but not later than 7 days after the acceptance of his tender, the contractor shall submit to the Executive Engineer for his approval, a time schedule to carry out works. The contractor shall whenever required by the Engineer-in-charge, furnish for his information arrangements for carrying out the work. The submission to and approval by Engineer-in-charge of such program or furnishing of such particulars shall not relieve the contractor of any of his duties or responsibilities under the contracts. In addition, the contractor shall have to furnish returns of work done by him, as may be directed by the Engineer-in-charge from time to time.

**EXECUTION**

The contractor shall have to execute various item of works strictly according to the order and time schedule approved by the Executive Engineer. Materials will also be tested for proper grading of Mix by Department before use.

**TECHNICAL STAFF AT SITE OF WORK**

The contractor shall have to employ full time technical staff for supervision of the work. Name of the technical staff employed by the contractor shall be intimated in writing to the Engineer-in-charge. Any change of technical staff during the execution of work should be intimated immediately in writing to the Engineer-in-charge.



## TENDER DOCUMENT No.-21\_10 लखनऊ विकास प्राधिकरण

### SITE OFFICE

The contractor shall establish and maintain a site office under his authorized representative/technical staff. All relevant documents shall be kept in the site office.

### ORDER BOOK

A site order book shall be maintained at the site of work in which instructions shall be given to the contractor as and when necessary. These instruction/orders, shall have to be signed and complied by the Contractor or his authorized representative. The entries in 'Site Order Book' shall be treated as proper notice serving upon the contractor in terms of his contract.

### LIGHTING ARRANGEMENT

The contractor shall make his own arrangement for lights during the fag end of the day in case the work is likely to be delayed due to unavoidable circumstances.

### TRAFFIC CONTROL

The contractor shall take all measures necessary for the safety of traffic during execution of work and shall provide, erect and maintain such barricades, reflective signs and caution boards, making flags, lights flagmen as necessary or as directed by the Engineer-in-charge for smooth and safe flow of traffic during execution or work. The contractor shall ensure to proper maintenance of pattries in 2.5m. width during execution of the bituminous work and it shall be kept always damp by regularly watering to avoid nuisance. In case of any casuality taking place at the work site, the contractor shall be solely responsible for payment of any compensation etc. to the aggrieved party.

### SUSPENSION OF WORK

The contractor on the written order of the Executive Engineer/Assistant Engineer shall suspend the progress of the works or any part thereof, for such time and in such manner as may be considered necessary and during such suspension shall properly protect and secure the work as far as necessary in the opinion of the Executive Engineer. Nothing extra shall be paid to the contractor if such a suspension is necessary for proper execution of the work by reason of weather or by some default or the contractor or necessary for safety of the work or any part thereof.

### SAMPLES

Contractor shall make laboratory with sufficient arrangement of testing facilities, appliances and laboratory technicians etc. at site and shall always co-operate in procurement of samples, conduction tests, as may be directed and no extra payment shall be made for them. Test samples shall be taken carefully in accordance with the I.S.I. method of sampling, no plea shall be entertained on this account. Job Mix Formula for B.M. and S.D.B.C. shall be done from any reputed authority by the contractor on his cost.

### TESTING MATERIALS

All materials and workmanship shall be of the respective kind described in the contract and in the accordance with Engineer-in-charge instructions and shall be subjected from time to time to the testes mentioned under specifications. The contractor shall provide such assistance, labour and materials as are normally required for examining measuring and testing of the works and quantity weight or quality of materials used and shall supply materials, sufficiently in advance for testing as mentioned under specifications. The materials used subsequently for





## **TENDER DOCUMENT No.-21\_10** **लखनऊ विकास प्राधिकरण**

execution of the work shall strictly conform to the quality and sample approved. Necessary test for which facilities are not available locally or at site shall be conducted in the nearest available laboratory research institute, Lucknow or any other reputed technical institution. Cost of such testing and forwarding of sample to the laboratory etc. shall be borne by the contractor and nothing extra shall be paid on this account. Regular quality control test registers shall be maintained by the contractor.

### **ROYALTIES AND TAXES ETC.**

The contractor shall pay all royalties, license fee, other charge at quarry, octroi duties, custom duties, toll taxes, trade tax and any other local taxes as may be levied. No passes for octroi or toll levied by local bodies on toll bridges shall be issued by the Department. Rate shall inclusive of the same. Nothing extra shall be paid due to fluctuations in the cost of materials, machines, bitumen, P.O.L., labour and all types of taxes etc.

### **COMPLIANCE WITH LOCAL BYE LAWS**

The contractor shall throughout the continuance of the contract and in respect of all matters arising out of performance thereof, conform with all required regulating and bye-laws of the local or other authorities which may be applicable to the works.

### **ROAD TRANSPORT**

The contractor employing motor vehicles for transport of material shall abide by provisions of the Motor Vehicles Act.

### **DAMAGES BY RAINS, ACCIDENTS OR NATURAL CALAMITIES**

No payment will be made to the contractor for damage caused by rains, accidents or other natural calamities during the progress of work. No claim whatsoever shall be entertained on this account.

### **DEFAULT OF CONTACTOR IN COMPLIANCE**

Constant defiance of the instructions of Engineer-in-charge on the part of the contractor or his authorized agent will make the contract will liable to be terminated.

### **CLEARANCE OR SITE ON COMPLETION**

The contractor shall at all times keep the premises free from accumulated waste materials or rubbish caused by his employees on the works and on completion of the work, he shall clear away and remove from site all surplus materials, rubbish and temporary work of any kind and fill up borrow pits dug by him. He shall leave whole of the site and work clean and in a workmanlike condition to the entire satisfaction of the Engineer-in-charge.



**TENDER DOCUMENT No.-21\_10**  
**लखनऊ विकास प्राधिकरण**  
**SCHEDULE – 'G'**

कार्य का नाम : सी0जी0 सिटी योजना स्थित पराग चौराहे से कैंसर संस्थान एवं मेडिकल विश्वविद्यालय तक हाईमास्ट, स्ट्रीट लाईट एवं पैनल के सुदृढीकरण का कार्य।

Sl.No.	Name	Qty	Unit	Rate
1	Supply and laying of <b>Aluminium conductor PVC insulated armoured served sheathed cables</b> 1100 Volts grade at a depth of 750 mm below ground level over a cushion of 75 mm. thick sand all around and protected with burnt bricks on sides and on top. On surface the cable run shall be fixed on M.S. clamps etc. of suitable size or as directed by the Engineer-Incharge, complete in all respect. The armouring of the cable shall be properly connected with the earth conductor by clamps etc. <b>(SI No : 501/2018)</b>			
(a)	10 sq. mm 4 core (501 (h)/2018)	950.00	Mtr	327.00
(b)	25 sq. mm 3-1/2 core (501 (j)/2018)	100.00	Mtr	373.00
(c)	95 sq. mm 3-1/2 core (501 (n)/2018)	110.00	Mtr	700.00
2	Supply and Fixing of 100 Amp. 4 Pole. Isolator CAT-A (SI No : 1007 ©/2018)	16.00	Nos	1365.00
3	S&F of 80 to 100 Amp 4 pole MCCB (16 KA) Thermal Magnetic release (SI No : 1021/2018)	8.00	Nos	6300.00
4	SITC of LED Driver for LED Fitting Approved Make as per direction of E/Ic. <b>(PSR)</b>			
(a)	90 watt to 110 watt	100.00	Nos	1378.00
(b)	120 watt to 190 watt	90.00	Nos	1496.00
5	SITC of 2.5 Sqmm 2 Core Size of PVC insulated sheathed flate twin Aluminum conductor 1100 Volt grade ISI approved as per direction of E/Ic. <b>(PSR)</b>	6.00	Coil	1915.20
6	SITC of 1.5 Sqmm 3 core 1100 Volt Grade LT Control Multistand Copper Unarmoured Cable as per direction of E/Ic. <b>(PSR)</b>	320.00	Mtr	127.00

**J.E. (E/M)**

**A.E. (E/M)**

I/we here by offer to execute the above work on .....%  
above/below (in figures) .....above/below (in words).

**Signature of Contractor**

**Address. :**

**Phone/Mobile No.:**