

निविदा-प्रपत्र

1. कार्य का नाम: अनंत नगर आवासीय योजना (मोहान रोड) के अन्तर्गत ग्राम-कलियाखेड़ा स्थित मन्दिर के बाउण्ड्रीवाल का कार्य।

2.

कार्य का नाम	बी0ओ0क्यू0 धनांक (रु0)	प्रतिभूति धनराशि (रु0)	समय	श्रेणी	निविदा मूल्य (रु0)
अनंत नगर आवासीय योजना (मोहान रोड) के अन्तर्गत ग्राम-कलियाखेड़ा स्थित मन्दिर के बाउण्ड्रीवाल का कार्य।	8,18,558.00	40,900.00	30 दिन	श्रेणी-डी सिंगल बिड	650.00 +18% GST

3. निविदा प्रपत्र निविदा सूचना में दी गई अवधि में वेबसाइट अथवा "http://www.ldaonline.in" से डाउन-लोड किये जायेंगे तथा पूर्ण रूप से भरे हुए एवं हस्ताक्षरित निविदाएं सीलबन्द लिफाफे में निविदा सूचना में अंकित तिथियों को निर्धारित स्थान-आयुक्त, लखनऊ मण्डल के नजारात कक्ष, लखनऊ कार्यालय, जिलाधिकारी, लखनऊ कार्यालय के कलेक्ट्रेट स्थित कक्ष संख्या-25 तथा प्राधिकरण के नवीन भवन, गोमती नगर, लखनऊ में रखे निविदा बाक्स में डाले जा सकेंगे।
4. निविदा के साथ दी जाने वाली प्रतिभूति की धनराशि, कार्य पूर्ण करने हेतु निर्धारित समय, कार्य की श्रेणी व अन्य शर्तें एवं विवरण निविदा सूचना में अंकित शर्तों, विवरण एवं 'नोट' के अनुसार लागू होगी। निविदा सूचना निविदा प्रपत्र का एक अंश है।
5. समस्त निविदाओं हेतु प्रतिभूति की धनराशि अधिशासी अभियंता, ल0वि0प्रा0 को न्यस्त एन.एस.सी./एफ.डी.आर./एन.एस.एस. के रूप में जमा करना होगा। यदि किसी निविदा के साथ उक्त प्रतिभूति धनराशि जमा नहीं होगी, तो ऐसी निविदाएं खोलते ही पुनः सील कर दी जाएंगी।
6. ठेकेदारों के चालित देयको से 10 प्रतिशत उस समय तक काटा जाएगा जब तक कि बकाया 5 प्रतिशत जमानत का धन प्राप्त नहीं हो जाता है वह 5 प्रतिशत अन्तिम देयक में ठेकेदार को दे दिया जायेगा तथा 5 प्रतिशत कार्य सन्तोषजनक होने के बाद 12 माह बाद अनुक्षण अवधि समाप्त होने के बाद वापस किया जायेगा।
7. किसी भी अथवा समस्त निविदाओं को अस्वीकृत कर देने का अधिकार सुरक्षित रहेगा इस सम्बन्ध में किसी भी व्यक्ति तथा व्यक्तियों द्वारा निविदा के अस्वीकृत होने के कारण को पूछा नहीं जा सकता है।
8. निविदा की स्वीकृति प्राप्त करने वाले ठेकेदार को स्वीकृत पत्र प्रमाण लेख पर हस्ताक्षर करने होंगे।
9. किसी भी निविदा पर विचार नहीं किया जायेगा जब तक कि उसके साथ अग्रिम धनराशि जमा करने की रसीद अथवा निविदा सूचना के अनुसार अग्रिम धनराशि संलग्न न होगी।
10. निविदा की दर तथा जोड़ को शब्दों तथा अंकों में स्पष्ट रूप से भरा जायें तथा कोई भी कटिंग व ओवर राईटिंग न की जायेगी अन्यथा निविदा अस्वीकृत कर दी जायेगी।
11. यदि निविदा की स्वीकृति प्राप्त करने वाले ठेकेदार 15 दिन के अन्दर स्पष्ट रूप से कान्ट्रेक्ट पर हस्ताक्षर नहीं करेगा तो निविदा के साथ जमा किया हुआ धन जब्त कर लिया जायेगा तथा निविदा की स्वीकृति वापस कर ली जायेगी।
12. ठेकेदार अपनी निविदा में दर उसी प्रकार से भरेगा जिस प्रकार से निविदा पत्र में मांगी गयी हों।
13. निविदा देने की तिथि से रु0 50,000.00 से कम की निविदा 4 माह तक वैध रहेगी तथा इसके ऊपर के धनराशि की निविदा 6 माह तक वैध रहेगी।
14. जो निविदा पता ठेकेदार का निविदा में मिलेगा वही पता मान्य होगा और इस पते पर भेजी गई डाक यदि डाकखाने से किसी कारण से वितरित न होकर वापस हो जाती है तो समझा जायेगा कि ठेकेदार द्वारा स्वीकार कर ली गई है।
15. प्रत्येक निविदा के साथ अलग से अग्रिम धनराशि होनी चाहिए, दूसरे निविदा के साथ लगी अग्रिम धनराशि मान्य न होगी।
16. पुरानी सिक्क्योरिटी या अग्रिम धनराशि जो विभाग द्वारा वापस की जाती है उसको अग्रिम धन के रूप में इंगित किया जायेगा तो मान्य न होगी।
17. प्रत्येक कार्य के निविदा प्रपत्र की मूल प्रति विभाग में सुरक्षित रखी गयी है। प्राप्त निविदाओं में किसी भी प्रकार की भिन्नता स्वीकार योग्य नहीं होगी एवं विवाद की स्थिति में मूल प्रति ही अंकित होगी।
18. प्रत्येक कार्य की निविदा के लिफाफे पर कार्य का नाम स्पष्ट रूप से अंकित होगी।
19. सभी साधारण एवं विशेष शर्तें/नियमों का पालन न होने पर निविदा मान्य न होगी और ठेकेदार को डिबार कर दिया जायेगा एवं ब्लैक लिस्ट भी किया जा सकता है।

हस्ता0
प्रमाणित —
प्रधान लिपिक {अभि0 विभाग}

ठेकेदार के हस्ताक्षर
तथा पता :

हस्ता0
अधिशासी अभियन्ता
लखनऊ विकास प्राधिकरण



TENDER DOCUMENT No.-159_19

लखनऊ विकास प्राधिकरण

कार्यालय मुख्य अभियंता
लखनऊ विकास प्राधिकरण
लखनऊ।

पत्रांक :- 159/ई-निविदा/मु0/2025-26

दिनांक:- 14/10/2025

ई-निविदा आमंत्रण सूचना

लखनऊ विकास क्षेत्र में निम्नलिखित कार्यों हेतु लखनऊ विकास प्राधिकरण या अन्य विकास प्राधिकरणों में पंजीकृत अथवा आवास एवं विकास परिषद में पंजीकृत ठेकेदारों से ऑनलाइन निविदाएं आमंत्रित की जाती हैं। कार्य से सम्बंधित विस्तृत निविदा-नोटिस तथा डाफ्ट निविदा-प्रपत्र लखनऊ विकास प्राधिकरण की वेबसाइट "https://ldalucknow.in" पर देखा जा सकता है, जिसमें धरोहर धनराशि, निविदा डालने की तिथि, श्रेणी, कार्य पूर्ण करने की अवधि एवं ई-निविदा लागत तथा अन्य नियम व शर्तों का उल्लेख है। कार्य से सम्बंधित ई-निविदा-प्रपत्र वेबसाइट "http://etender.up.nic.in" पर उपलब्ध होंगे तथा ई-निविदा करने होंगे।

क्र.	कार्य का नाम	अनुमानित लागत (रु. लाख में)	ठेकेदार की श्रेणी / बिड पद्धति	निविदा प्रपत्र एवं निविदा प्रक्रिया का मूल्य (रुपये में)	धरोहर राशि (रुपये में)	निविदा पोर्टल पर निविदा प्रपत्र डाउनलोड / अपलोड करने की प्रारम्भ तिथि	निविदा पोर्टल पर निविदा प्रपत्र अपलोड करने एवं निविदा प्रपत्र का मूल्य व धरोहर धनराशि ऑन लाइन जमा करने की अंतिम तिथि एवं समय	ट्र. बिड निविदाओं की लक्ष्मी की बिड एवं सिंगल बिड निविदाओं की वित्तीय बिड खोलने की तिथि एवं समय	कार्य पूर्ण करने की अवधि
1	नवजल पार्कों के अंतर्गत लोहिया पार्क, नीबू पार्क, खोब पार्क व बेगम हजरत महल पार्क का एक वर्ष हेतु औद्योगिक अनुरक्षण का कार्य	105.1	B / Two bid System	4366	315300	16-October-2025	12-November-2025 12:00 AM	13-November-2025 03:00 PM	0 Year 12 Month 0 Day
2	तहसील गौसाईगंज, सरोजनी नगर के अंतर्गत ग्यु गुडोरा, अमोल, नया पुरवा, हसनपुर खोवली एवं अमौसी 1 में अगलबाड़ी का निर्माण कार्य।	79.87	B / Two bid System	4366	399300	16-October-2025	29-October-2025 12:00 AM	30-October-2025 03:00 PM	0 Year 6 Month 0 Day
3	अनंत नगर योजना के अंतर्गत सेक्टर 6 में पार्क (6/G-07) के निर्माण का कार्य	70.14	C / Two bid System	2950	350700	16-October-2025	05-November-2025 12:00 AM	06-November-2025 03:00 PM	0 Year 6 Month 0 Day
4	जनेश्वर मिश्र पार्क के गेट नं०-02 से दयाल पैराडाइस का रोहरे तक मौडीपन सिविल पर पिल लगाने के साथ-साथ अन्य कार्य।	60.88	C / Two bid System	2950	304400	16-October-2025	05-November-2025 12:00 AM	06-November-2025 03:00 PM	0 Year 3 Month 0 Day
5	लक्ष्मण पार्क एवं राजा जय लाल पार्क में विद्युतीकरण एवं प्रकाश व्यवस्था तथा 03 वर्ष के अनुरक्षण एवं संचालन का कार्य।	58.66	C / Two bid System	2950	293300	16-October-2025	05-November-2025 12:00 AM	06-November-2025 03:00 PM	0 Year 3 Month 0 Day
6	अनंत नगर योजना के अंतर्गत सेक्टर 3 में पार्क (3/G-03) के निर्माण का कार्य	53.26	C / Two bid System	2950	266300	16-October-2025	05-November-2025 12:00 AM	06-November-2025 03:00 PM	0 Year 6 Month 0 Day
7	गोमती नगर विस्तार योजना गंगोत्री विहार फेज-2 मकान सं०-16 से मकान सं०-65/15 ई तक रोड, नाली, इन्फ्रालाइटिंग टाइल्स लगाने का कार्य।	40.02	C / Two bid System	2950	200100	16-October-2025	29-October-2025 12:00 AM	30-October-2025 03:00 PM	0 Year 3 Month 0 Day
8	प्राधिकरण कार्यालय गोमती नगर के पुराने भवन में फायर फाइटिंग से सम्बंधित कार्य।	36.01	C / Two bid System	2950	180000	16-October-2025	29-October-2025 12:00 AM	30-October-2025 03:00 PM	0 Year 1 Month 0 Day
9	ऐशबाग योजना के अंतर्गत मोहल्ला करेहटा में कल्लू होटल से आंतरिक छतिशत मार्ग व गलियों के सुदृढीकरण का कार्य।	33.59	C / Two bid System	2950	167900	16-October-2025	29-October-2025 12:00 AM	30-October-2025 03:00 PM	0 Year 4 Month 0 Day
10	टिकैट राय योजना के फेज- 02 के भूखंड संख्या MIG 66 से MIG-72 के सामने स्थित पार्क का निर्माण कार्य।	25.19	C / Two bid System	2950	126000	16-October-2025	29-October-2025 12:00 AM	30-October-2025 03:00 PM	0 Year 3 Month 0 Day
11	KANPUR ROAD YOJNA STHIT GAUTAM BUDHIHA PARK NO-02 AND 03 ME NAYA PANEL STHAPIT KARAYE JANE KA KARYA	8.54	D / Single Bid	767	42700	16-October-2025	27-October-2025 12:00 AM	28-October-2025 03:00 PM	0 Year 1 Month 0 Day
12	Kanpur road yojna sthith smratu upvan park me mud pump and transformer appurti and sthapana tatha open gym me mini highmast ki shtapana ka karya	8.52	D / Single Bid	767	42600	16-October-2025	27-October-2025 12:00 AM	28-October-2025 03:00 PM	0 Year 1 Month 0 Day
13	जमुनाझील ऐशबाग में प्रकाश बिन्दुओं व फाउण्टेन के संचालन एवं विद्युत सामग्री की आपूर्ति का कार्य।	8.46	D / Single Tender	767	42300	16-October-2025	27-October-2025 12:00 AM	28-October-2025 03:00 PM	0 Year 1 Month 0 Day
14	आई०टी० सिटी योजना के अंतर्गत मास्टर रोड आर-5 बैनर 0 से 590 मी० तक सब ग्रेड सड़क का कार्य।	8.35	D / Single Bid	767	41700	16-October-2025	27-October-2025 03:00 PM	27-October-2025 04:00 PM	0 Year 1 Month 0 Day



15	आई०टी० सिटी योजना के अन्तर्गत मास्टर रोड आर-5 सेज 591 से 1180 मी० तक सब ग्रेड सड़क का कार्य ।	B.35	D / Single Bid	767	41700	15-October-2025	27-October-2025 03:00 PM	27-October-2025 04:00 PM	0 Year 1 Month 0 Day
16	अनंत नगर आवासीय योजना (मोहान रोड) के अन्तर्गत ग्राम-कास्थिया खेड़ा स्थित मंदिर के इंटरलॉकिंग का कार्य ।	B.32	D / Single Bid	766	41600	16-October-2025	27-October-2025 03:00 PM	27-October-2025 04:00 PM	0 Year 1 Month 0 Day
17	आई०टी० सिटी योजना के अन्तर्गत सब रोड आर-23 सेज 291 से 580 मी० तक सब ग्रेड सड़क का कार्य ।	B.28	D / Single Bid	767	41400	16-October-2025	27-October-2025 03:00 PM	27-October-2025 04:00 PM	0 Year 1 Month 0 Day
18	आई० टी० सिटी में विभिन्न स्थानों पर बोर्ड लगाने का कार्य पार्ट - ए	B.22	D / Single Bid	767	41100	16-October-2025	27-October-2025 03:00 PM	27-October-2025 04:00 PM	0 Year 1 Month 0 Day
19	अनंत नगर आवासीय योजना (मोहान रोड) के अन्तर्गत ग्राम-कास्थिया खेड़ा स्थित मंदिर के बाऊंडरीवाल का कार्य ।	B.19	D / Single Bid	767	40900	16-October-2025	27-October-2025 03:00 PM	27-October-2025 04:00 PM	0 Year 1 Month 0 Day
20	कानपुर रोड योजना सेक्टर-डी1 में स्थित भवन संख्या SS III D1-93-94 से SS III D1-222 के सामने सेक्टर जी में स्थित ग्रीन बेल्ट बी रेंजई-पुताई का कार्य।	B.18	D / Two bid System	767	40900	16-October-2025	27-October-2025 03:00 PM	27-October-2025 04:00 PM	0 Year 1 Month 0 Day
21	नवतुल पार्क के अन्तर्गत बेगम हजरत महल पार्क, राजा राम पाल सिंह पार्क एवं जूना देवी पार्क में कुड़ा डम्पिंग स्टर बनाने का कार्य।	B.11	D / Single Tender	767	40600	16-October-2025	27-October-2025 03:00 PM	27-October-2025 04:00 PM	0 Year 1 Month 0 Day
22	मान्यवर श्री काजीराम जी ग्रीन ईको गार्डन में सीढ़ियों का निर्माण कार्य।	B.03	D / Single Bid	767	40100	16-October-2025	27-October-2025 03:00 PM	27-October-2025 04:00 PM	0 Year 1 Month 0 Day
23	JANKIPURAM YOJNA SECTOR J STHITH SRASTI APARTMENT ME STHAPIT VIDHUT SANYANTRO KE NIYAMIT RAKH RAKHAHV AND SANCHALAN HETU ELECTRICIAN AND HELPER KI TAINATI KA KARYA (01 YEAR)	5.44	D / Single Bid	767	27200	16-October-2025	27-October-2025 12:00 AM	28-October-2025 03:00 PM	1 Year 0 Month 0 Day
24	कानपुर रोड योजना स्थित गौतम बुद्ध पार्क नम्बर-02 व 03 में स्थापित 02 नग 7.5 एम्पगी0 मोटर की रिजर्वतपमेटर एवं झील की सफाई हेतु मड पम्प लगाने का कार्य।	5.24	D / Single Bid	767	26200	16-October-2025	27-October-2025 03:00 PM	27-October-2025 04:00 PM	0 Year 1 Month 0 Day
25	KANPUR ROAD YOJNA JYOTIBA FULE ZONAL PARK ME STHAPIT 400 KVA TRANSFORMER KI REPAIRING KA KARYA	3.62	D / Single Bid	767	18100	16-October-2025	27-October-2025 03:00 PM	27-October-2025 04:00 PM	0 Year 1 Month 0 Day
26	BAL VIHAR COLONY FARIDNAGAR ME AWAS NO-100 SE 104 TAK KE SAMNE STHITH PARK ME BACHOO KE JHOOLE LAGANE KA KARYA	1.73	Experienced and Specialized Firms / Single Bid	767	8600	16-October-2025	27-October-2025 03:00 PM	27-October-2025 04:00 PM	0 Year 1 Month 0 Day

नियमावली धर्तः-

1. काम सं-5 एवं 6 के अंतर्गत निविदा प्राप्त का मूल्य एवं धरोहर राशि HODFC Bank की वेबसाइट <https://ida.procure247.com> माध्यम से अनलाइन जमा करनी होगी।
उक्त वेबसाइट के माध्यम से निविदा प्राप्त का मूल्य "Tender Fee" मद में एवं धरोहर राशि "EMD" मद में जमा करनी होगी। 03090 लोक निर्माण विभाग के शासनादेश सं-692/23-07-2024/2-08 दिनांक 09.08.2024 के अनुसार निर्माण/विकास कार्य हेतु आमंत्रित निविदाओं में निविदादाता द्वारा निविदा लागू रखकृत (बीओआयएस्यू) लागू हो 10 प्रतिशत कम होने पर कोई अतिरिक्त परफार्मेंस सिक्वीटी नहीं ली जायेगी। निविदादाता को निविदा दाखल 15 प्रतिशत व इससे अधिक भिन्न जाने पर अतिरिक्त सिक्वीटी(एफ/परफार्मेंस गारंटी) 15 प्रतिशत निम्न होने पर 10 से अधिक अतिरिक्त 5 प्रतिशत हेतु 15 प्रतिशत से अधिक निम्न होने पर 15 प्रतिशत के पक्षत प्रत्येक 1 प्रतिशत के हिसाब इ प्रत्येक अतिरिक्त परफार्मेंस सिक्वीटी(एफ/परफार्मेंस गारंटी) जमा करणी जायेगी, जिसे एक निमित्त बिले जाने के 15 दिवस के अवधिनि (अनुभवमान से पूर्ण) जमा करना होगा। निष्पत्ति सम्बंधीकरण के अन्तर्गत अतिरिक्त सिक्वीटी(एफ/परफार्मेंस गारंटी) प्राधिकरण में जमा न कराये जाने पर सम्बंधित निविदादाता को 01 वर्ष की अवधि हेतु निविदाओं में प्रतिभाग किये जाने से डिबार किया जायेगा व निविदा की जमानत धराराशि (रजमंडमडी) को भी जप्त कर लिया जायेगा। अतिरिक्त सिक्वीटी(एफ/परफार्मेंस गारंटी) का 50 प्रतिशत निम्न करने के अंतिम भुगतान के पश्चात् व शेष 50 प्रतिशत अनुभवमान में प्राप्तिप्राप्ति Defect liability period के पश्चात् अनुभवमान किया जायेगा।
2. निविदाकीडरीदों में जीएसटी(0%) अथवा कोई कर समझित नहीं है। जीएसटी(0%) नियमानुसार अतिरिक्त देय होगा।
3. निविदा प्राप्त 03090 लेबरकुनि कार्यालय की वेबसाइट <https://tendering.in> पर देखें जा सकते हैं तथा इसी वेबसाइट से डाउनलोड/अपलोड भी किये जा सकते। इसचुक ठेकेदारों से अनुरोध है कि वे नियमित रूप से उक्त वेबसाईट एवं सहायक विकासप्राधिकरण की वेबसाईट <https://ddakulacknow.in/> को देखते रहें क्योंकि प्रकाशित निविदाओं के सम्बंध में कोई बदलाव अथवा सूचना उक्त दोनों वेबसाईट पर ही उपलब्ध करायी जायेगी। तत्कालीन बिड़मु अह निविदादाताओं को तिथिपूर्व बिड़ सूचनाओं की तिथि एवं समय की सूचना वेबसाईट <https://tendering.in> पर अपलोड दी जायेगी। सहमत सेवा प्रदाता से उपलब्ध कराये हुए डिजिटल सिग्नेचर शारक प्राधिकरण में पंजीकृत ठेकेदारों द्वारा ही ऑनलाइन निविदा दाखल जा सकती है।
4. कोई का मात्रा में कमी/अधिकारी अथवा बिभिन्नकर करने अथवा किसी भी निविदा को बिना कारण बिना वारे निरस्त करने का अधिकार उपायास्था, सहायक विकास प्राधिकरण में निहित है, बिचिके बिस्सूद्ध निविदादाताका कोई बेल्ले मान्य नहीं होगा।
5. निविदाकीसीकृति की दशा में जमानत धराराशि हेतु सीकृत कार्य लागत की 10 प्रतिशत धराराशि में से उक्त कॉलम 6 के अनुसार जमा धरोहर धराराशि को समावेष्टित करते हुए शेष धराराशि ठेकेदार द्वारा देय होगी।
6. निविदादाता को आवक्य विभाग, श्रम विभाग एवं जीएसटीमें में पंजीकरण कराना अनिवार्य होगा। शाशन द्वारा समय-समय पर आग्यकर, लेवर रूस एवं अन्य करों की कटौती ठेकेदार के बिनी से नियमानुसार की जायेगी।
7. 03090 भवन एवं अन्य यंत्रिप्राम कर्मकर नियोजन तथा सेवा शर्त बिगिनियम नियमावली वर्ष-2009 के बिगिनियम 24(2) के अन्तर्गत प्रकाशित सिंधिदा हेतु श्रम बिभाग में किस प्रकार पंजीकरण कराना अनिवार्य है। अतःअनुभवमान गहन के पश्चात् उक्त पंजीकरण प्रमाण-पत्र पूर्वकर कराना होगा, बिचिके उपरांतर ही चलिंद देय का भुगतान किया जायेगा।
8. रेटकराकोनैलेशन में पंजीकृत व्यक्ति एवं आराराषिक रिक्वाइर वाले निविदादाताओं को निविदा प्रक्रिया में भाग लेने की अनुमति नहीं है। साथ ही यदि निविदादाता का सगा सम्बन्धी (first blood relation & their dependant) सहायक विकास प्राधिकरण में कार्यरत है तो उसे भी निविदा प्रक्रिया में भाग लेने की अनुमति नहीं है।
9. निविदादाता द्वारा दिहिये दखलेबो/प्रमाण-पत्री केगलत एवं/अथवा एवं कार्य/अनुभवमान की सीकृति को तत्काल निरस्त करते हुए ठेकेदारद्वारा जमा धरोहर/जमानत धराराशि को जप्त कर लिखा जायेगा तथा ठेकेदार को काही सीकृति में डाल दिया जायेगा।
10. सहायक विकास प्राधिकरण या अन्य किसी भी विकास प्राधिकरण/ए/आवास एवं विकास परिषद में पंजीकृत फर्मसू निविदा में प्रतिभागकर सकती है। सहायक विकास प्राधिकरण में पंजीकृत निविदादाताओं के अतिरिक्त अन्य निविदादाताओं को सम्बंधित बिभाग का पंजीकरण प्रमाण-पत्र पुस्तुत करना होगा।सहायक निविदादाताओं को अनुभव के समय सहायक विकास प्राधिकरण में नियमानुसार अपनी फर्म का पंजीकरण कराना होगा।
11. आमंत्रित निविदा में ऐसकार्य, बिचामे अन्य विकास के साथ-साथ बिटुमिनस सड़क सम्बन्धी कार्य भी समझित होंगे, ऐसी स्थिति में कार्य की कुल बीओआयएस्यू फ़ॉनांक से 50 प्रतिशत तक के बिटुमिनस सड़क सम्बन्धी कार्य को अनुमानत रूप 25.00 लाख की धराराशि से कम न हो, के बिटुमिन सम्बन्धी कार्य होने पर सख्त का लाहट होने पर शायत से के साहा हाट मिंसालाहट हुए उससे सम्बंधित दूसर एण्ड लाहट की उपलब्धताअनुसार, को नीटरी से प्रमाणीत करते हुए प्रमाण-पत्र संलग्न करना पर क्या बिचारये लाहट पर लिखे जाने के बिचामे सम्बंधित श्रेणी के पंजीकृत ठेकेदार द्वारा का बिचामे बिचिरेषिकसे लिख निविदा आमंत्रित की गयी है, हेतु सहायक विकास प्राधिकरण, 03090 लोक निर्माण विभाग व एफ/एफ/एफ/आईएम में डॉट मिंसालाहट पर रिक्वाइरठ ठेकेदार (रिक्वा के साथ वांछित दल व घनत्वस हो) से ही सब रिक्वाइरत कार्यावधि से अनुभवमान/लौरी पंजीकृत करता हुए अनुभवमान/लौरी व मोदीरी के ओराराषिक के प्रदान भी निविदेके साथ संलग्न किया जाना आवश्यक होगा, (लोक निर्माण बिभाग, 03090 के संख्या-795/बीसीटी-1(एफ/एफ/ 401एमटी-1)/2020, दिनांक 16.10.2020) के अनुसार निर्धारित कार्य एवं अन्तर्गत तथा निविदा में प्रतिभाग किया जा सकता, अन्यथा प्राप्त निविदा अंगी नहीं होगी। निविदा में Lessor एवं Lessee में से एक पक्ष द्वारा ही प्रतिभाग किया जाना अनुमत्य होगा। लौरी की अवधि/काल हेतु पीरिएड अवधि में Lessor द्वारा Hot Mix Plant उपयोगहेतु Lessee के अतिरिक्त निविदा की अन्य को उपलब्ध नहीं कराया जायेगा। एवं प्रमाण सं 200/00-लाभ तककी लागत की निविदाओं में ही लागू होगे, इससे अधिक लागत के कार्य का सहायिता होगा अधिकांश है।
- हॉट मिक्स प्लांट प्राधिकरण मुख्यालय/कार्यस्थल से 50 कि०मी० परिधि में स्थापित होगा अनिवार्य होगा। बिटुमिनस सड़क सम्बन्धी कार्य में बीओएस, बीसीसी, एससीसीबीसीसी, डेट कोट, प्राइम कोट, जीएसबीबी,

<https://enq.idalucknow.in/TNDR/RFP/NIT?a=O6biX9ifE3bQIS1th2HdJilhAQ3tvzcYWRBE34pVxCAiovQrihiioLzY/uraHBGafkvov+4vA9RH/odYin+MinL...> 5/8



TENDER DOCUMENT No.-159_19

लखनऊ विकास प्राधिकरण

डबल्यूएमओएमओ आदि कार्य सम्मिलित हैं।

- इसीप्रकार सड़क के कार्यों के अंतर्गत जहाँ WMM का कार्य पक्का रू० 20.00 लाख से अधिक का सम्पादित किया जाना है, वहाँ पर सम्बंधित कार्यदायी एजेंसी/फर्म के पास स्वयं का अथवा स.वि.प्र./लो.नि.वि./एन.एस.ए.आई. में पंजीकृत ठेकेदारों से किराये/लीज पर अनुबन्धित Computerised Wetmix Plant (Capacity 75 TPH) का होना अनिवार्य है तथा WMM के laying सम्बंधित कार्य समुचित मशीनरी (Paver Finisher) आदि के द्वारा ही कराया जाना सुनिश्चित किया जाएगा। भविष्य के कार्यों में बिड के साथ प्लाण्ट के स्वामित्व के सम्पूर्ण कागजात संलग्न होना भी अनिवार्य होगा तथा निविदा डालते जाने के समय प्राधिकरण मुख्यालय/कार्यालय से प्लाण्ट 50 कि०मी० की परिधि में होना अनिवार्य होगा। किस हेतु बाण्ण पत्र, अनुबंध प्राप्त इत्यादि सम्बन्धित प्राप्त उपरोक्तानुसार हॉट मिक्स प्लाण्ट के अनुसार ही संलग्न करने होंगे।
- बिटुमिनस सड़क निर्माणके कार्य में एस.डी.बी.सी. (टीप लेयर) का कार्य प्लास्टिक वेस्ट मिक्स करके एवं तदनुसार मिक्स डिजाइन करके कराया जाएगा। प्लास्टिक वेस्ट को हॉट मिक्स प्लाण्ट में फीड करने हेतु निर्धारित स्थान पर आवश्यक मशीनरी का प्राविधान होना आवश्यक है।
- पंजीकृत ठेकेदार अपनीश्रेणी के अलावा एक श्रेणी नीचे तक भी कार्य ले सकेंगे। यदि एक श्रेणी से अधिक उच्च श्रेणी के पंजीकृत ठेकेदार द्वारा निविदा डाली जाती है, तो उसकी थरोहर राशि जम्मा कर ली जाएगी तथा पुनरावृत्ति की स्थिति में फर्म को डिबार/ब्लैक-लिस्ट किया जा सकता है।
- निविदा खोलने की तिथि को अवकाश की स्थिति में निविदा अगले कार्य दिवस में खोली जाएगी।
- अर्थात् निविदा मान्य नहीं होगी।
- निविदा आमन्त्रण सूचना के नियम व शर्तों तथा निविदा प्रपत्रों में उल्लिखित नियम व शर्तों में यदि कोई भिन्नता होती है तो निविदा आमन्त्रण सूचना की नियम व शर्तें ही मान्य होगी।
- निविदा की दरे निविदा प्राप्ति की अंतिम तिथि से 90 दिन तक वैध होने के सम्बन्ध में रू० 100/- के नॉन जुडिशियलस्टैम्प पेपर पर अप्ररटेकिंग निविदा के साथ अपलोड करनी आवश्यक होगी।
- निविदादाता द्वारा टू-बिड निविदा की तकनीकी बिड के साथ अपलोड किये जाने वाले प्रारंभ-पत्र, चरित्र प्रमाण-पत्र, हैसियत प्रमाण-पत्र, अनुभव प्रमाण-पत्र, आवश्यक मशीनरी, बिड कैपेसिटी विवरण (वर्तित कार्यों के विवरण सहित), तकनीकी स्टाफ से सम्बंधित विवरण, बैंक प्रमाण-पत्र, लिक्विड एसेट (बैंक सॉल्वेन्सी) एवं बाण्ण पत्र आदि वैधता अवधि के अन्तर्गत के ही अपलोड किये जाने आवश्यक है।
- तकनीकी बिड में संलग्न किये जाने वाले वर्णित प्रपत्रों की नम्बरिंग करते हुए, उनकी विषय सूची (किस पृष्ठ पर कौन सा प्रारंभ संलग्न है) संलग्न करनी आवश्यक होगी। साथ ही वर्णित प्रपत्रों का स्वप्रामाणित भी होना आवश्यक होगा।
- उपरोक्त 14, 15, 16, 17, 18, 19, 20, 21, 22, 24, 25, 26 पर अंकित कार्यों हेतु सामान्य निविदाएं आमंत्रित की जाती हैं, जिनके निविदा प्रारंभ वेबसाइट <https://ldalucknow.in> से डाउनलोड किये जा सकेंगे एवं प्राधिकरण के नवीन भवन स्थित मुख्य अभियंता कक्ष में रखे निविदा बाक्स में सप्ताह (8) में अंकित तिथियों में खले जा सकेंगे अथवा रजिस्टर्ड डाक से अपराह्न 3:00 बजे तक भेजे जा सकते हैं, परन्तु निर्धारित समय के पश्चात प्राप्त निविदाओं पर विचार नहीं किया जाएगा। प्राप्त निविदाएं कॉलम-9 में अंकित तिथि व समय पर ठेकेदारों अथवा उनके अधिकृत प्रतिनिधियों (यदि उपस्थित हुए) के समक्ष प्राधिकरण के नवीन भवन में मुख्य अभियंता कार्यालय कक्ष में खोली जाएगी। इन कार्यों की निविदाओं हेतु प्रतिभूति की धनराशि अधिशासी अभियंता, लखनऊ के पक्ष में एन.एस.सी./एफ.डी.आर./एन.एस.एस. के रूप में जमा करना होगा। यदि किसी निविदा के साथ उक्त प्रतिभूति धनराशि जमा नहीं होगी, तो ऐसी निविदाएं खोलते ही पुनः खोलकर दी जाएगी। निविदा मूल्य नगद/बैंक ड्राफ्ट के रूप में सचिव, लखनऊ विकास प्राधिकरण के पक्ष में देय होगी, जो वापस नहीं होगी।

मुख्य अभियंता

प्रतिलिपि:

- उपाध्यक्ष महोदय के अवलोकनार्थ।
- सचिव महोदय को सूचनाार्थ।
- वित्त नियंत्रक को सूचनाार्थ एवं आवश्यककार्यवाही हेतु।
- सम्बंधित अधिशासी अभियंताओं को इस निर्देश के साथ कि संबंधित कार्यों के निविदा प्रारंभसमय से प्राधिकरण की वेबसाइट <https://ldalucknow.in> / तथा e-tender Portal पर लॉड कराना सुनिश्चित करें तथा निविदा खोलते समय अनिवार्य रूप से उपस्थित रहें।
- पी.ए.(टी.) को इस आशय से प्रेषित कि वे लखनऊ विकास प्राधिकरण की वेबसाइट पर निविदा सूचना अपलोड कराएं।

मुख्य अभियंता



TENDER DOCUMENT No.-159_19
लखनऊ विकास प्राधिकरण

SCHEDULE 'A'

The work is to be done in connection with.....
.....

The site of work can be ascertained from the Assistant Engineer (Project Lucknow Development Authority, Lucknow).

The tenders are advised to inspect the site of the work Before tendering the rates so that they may fully acquaint themselves with the nature of the work to be done, the means of communication and availability of materials and water required for the work.

The contractor must complete the work in accordance with the specification and to the entire satisfaction of the Engineer Incharge within the specified period.

SCHEDULE 'B'

The drawings regarding this, this work can be seen in the office of Adhishashi Abhiyanta Lucknow Development Authority on any working day from 10 A.M. to 5 P.M.

SCHEDULE 'C'

-- NIL --

SCHEDULE 'D'

The following samples be submitted by the contractor within 10 days of the receipt of orders to start the work and subsequent supplies shall not be inferior to the samples approved.

1.	Bricks	10 Nos. Surkhi	1 Cft.	
2.	Coarse Sand	1 Cft.	Brick ballast	1 Cft.
3.	Local Sand	1 Cft.	Any other sample	Desired by the Engineer
4.	Hard stone grit	1 Cft.		

Materials specified by the Engineer from time to time and brought on the site of work shall occasionally be tested by the Engineer at the cost of the Contractor. The material rejected shall be removed by the contractor within 24 hours, failing which the rejected materials shall be removed or disposed of by the Lucknow Development Authority at the cost of the contractor.

SCHEDULE 'E'

1. All materials supplied by the contractor brought on the site shall be tested by the Engineer Incharge frequently to check up if they conform the specification of P.W.D.
2. All the rates as may be necessary shall be performed at the contractor's expenses and will have to make all necessary arrangement for conducting them and when called upon on to do so to the satisfaction of the Engineer.

SCHEDULE 'F'

All works specified herein shall be completed in all respect to the entire satisfaction of the Engineer Incharge and handed over to him or any persons nominated by to take over within a period ofmonths from the date of receipt written order to commence the work.



TENDER DOCUMENT No.-159_19
लखनऊ विकास प्राधिकरण

The contractor's responsibility shall, however, not & untill the maintenance period of one year or one rainy season with which ever is more from the date of completion is over is any defect is notified at the contractor's cost.

Individual portions of the work may be brought into use of the Lucknow Development Authority as each section is completed but maintenance period of one year or one rainy season which ever is more shall be finally counted from the date of entire work under the contract is finally completed and handed over.

SCHEDULE I

The department will supply the following materials at the rate mentioned against each.

SI. No.	Name of the material	Rate	Place of issue	Remarks
1-	Nil		Nil	
2-	Nil		Nil	

CONDITIONS

1. The Engineer and subordinate incharge shall be free inspect the godown of Contractor at any time.
2. Every effort will be made by the L.D.A. for continuous supply of the above Material but the department dose not guarantee for the same and it will have to be arranged by the contractor without any claim. It should carefullud noted by the contractor that no compensation whatsoever shall be given to them for any interruption in the work for want of supply of material form the L.D.A. or any other case whatsoever.
3. Material issued to the contractor shall be carted by them to the site of work at his own cost.
4. Stores supplied by the department, if found damaged or missing shall be recovered at double the rate of issue. In case of materials supplied free of cast the deductions shall be made at double the book value of the material.
5. Any other material not easily available in the market at the time of construction but existing in the department store can be issued at the store issue rate plus 10% or market rate whichever is higher on the written request of the contractor.
6. The contractor will have to make his own arrangement for the all T.P. machinery and other equipment required to complete the work under his contract.

Contractor.....
Dated.....
Witness.....
Dated.....



TENDER DOCUMENT No.-159_19
लखनऊ विकास प्राधिकरण

LUCKNOW DEVELOPMENT AUTHORITY LUCKNOW

SPECIAL CONDITIONS FOR WORK

All the work shall be carried out as per detailed U.P.P.W.D., U.P. JAL NIGAM, U.P. POWER CORPORATION LTD., M.O.S.T. (Road Wing) specifications for road and bridge work (third revision 1995) as the case may be, latest circulars and instructions issued time to time as per instructions of Engineer-in-charge and other inspecting officers.

EXTENT OF CONTRACT

The Contract comprises construction and completion of the specified job and the provisions of all labour, materials, T&P etc. and transport, temporary works etc. whether of temporary or permanent in nature required for the construction, completion and maintenance of the work.

INSPECTIONS OF THE SITE

The tenderer (s) must inspect and examine the site of work and its surroundings and satisfy himself/themselves before submitting his/their tender. He/they has/have to make sure of the positions of quarries and availability of required material from quarries mentioned in the specifications, topography of the site availability of labour and material and other amenities before tendering. No claim for additional work or extra work due to any of the above will be allowed.

ENTRIES IN TENDER

All entries by the tenderer should be in one ink and one hand/on prescribed bill of quantity only. Eraseres and overwriting are not permissible. All corrections should be neatly written and signed by the tenderer. Rate should be written in figures as well as in words. In case there is any variation, lower rate shall be treated as Tender rate.

CONDITIONAL/ INCOMPLETE TENDER

Conditional, incomplete, unsigned tenders will not be considered. Only those bidders who supply necessary proof/documents of possession of the required equipments in their bids should be considered as responsive for further evaluation.

ADDRESS OF CONTRACTOR

The contractor shall give his full permanent postal address. The postal receipt of the letters sent to him on this address shall be considered sufficient proof that they have been delivered to him.

ACCEPTANCE OF TENDER

The department shall have the right to accept or reject any or all the tenders or part thereof, without assigning any reason to contractor and no claim whatsoever shall be entertained on this account.

SIGNING OF TENDER DOCUMENTS

Contractor shall sign each page of tender documents before offering his tender and required stamp duty on the contract deed will be borne by the contractor.

COPY OF CONTRACT

On request, the Executive Engineer may furnish the contractor with a copy of the contract.

TIME OF COMPLETION

The time of completion as shown in this tender is for completion of the entire work.

EMPLOYMENT OF LABOUR

The contractor shall submit a daily report to the Engineer-in-charge regarding the total labour employed by him for the work and shall be bound to pay wages which shall not be less than the wages fixed under Minimum Wages Act.

LINE AND LEVELS

The contractor shall be solely responsible for setting out the works and for the correctness of the position, levels, dimensions and alignment according to the specification and shall provide all necessary assistance, instruments, pegs, sticks, poles and other materials, required for the purpose. The tender rates shall be deemed to include all this.

PROGRAMME AND RETURNS TO BE FURNISHED

As soon as practicable, but not later than 7 days after the acceptance of his tender, the contractor shall submit to the Executive Engineer for his approval, a time schedule to carry out works. The contractor shall whenever required by the Engineer-in-charge, furnish for his information arrangements for carrying out the work. The submission to and approval by Engineer-in-charge of such program or furnishing of such particulars shall not relieve the contractor of any of his duties or



TENDER DOCUMENT No.-159_19

लखनऊ विकास प्राधिकरण

responsibilities under the contracts. In addition, the contractor shall have to furnish returns of work done by him, as may be directed by the Engineer-in-charge from time to time.

EXECUTION

The contractor shall have to execute various item of works strictly according to the order and time schedule approved by the Executive Engineer. Materials will also be tested for proper grading of Mix by Department before use.

TECHNICAL STAFF AT SITE OF WORK

The contractor shall have to employ full time technical staff for supervision of the work. Name of the technical staff employed by the contractor shall be intimated in writing to the Engineer-in-charge. Any change of technical staff during the execution of work should be intimated immediately in writing to the Engineer-in-charge.

SITE OFFICE

The contractor shall establish and maintain a site office under his authorized representative/technical staff. All relevant documents shall be kept in the site office.

ORDER BOOK

A site order book shall be maintained at the site of work in which instructions shall be given to the contractor as and when necessary. These instruction/orders, shall have to be signed and complied by the Contractor or his authorized representative. The entries in 'Site Order Book' shall be treated as proper notice serving upon the contractor in terms of his contract.

LIGHTING ARRANGEMENT

The contractor shall make his own arrangement for lights during the fag end of the day in case the work is likely to be delayed due to unavoidable circumstances.

TRAFFIC CONTROL

The contractor shall take all measures necessary for the safety of traffic during execution of work and shall provide, erect and maintain such barricades, reflective signs and caution boards, making flags, lights flagmen as necessary or as directed by the Engineer-in-charge for smooth and safe flow of traffic during execution or work. The contractor shall ensure to proper maintenance of patties in 2.5m. width during execution of the bituminous work and it shall be kept always damp by regularly watering to avoid nuisance. In case of any casualty taking place at the work site, the contractor shall be solely responsible for payment of any compensation etc. to the aggrieved party.

SUSPENSION OF WORK

The contractor on the written order of the Executive Engineer/Assistant Engineer shall suspend the progress of the works or any part thereof, for such time and in such manner as may be considered necessary and during such suspension shall properly protect and secure the work as far as necessary in the opinion of the Executive Engineer. Nothing extra shall be paid to the contractor if such a suspension is necessary for proper execution of the work by reason of weather or by some default or the contractor or necessary for safety of the work or any part thereof.

SAMPLES

Contractor shall make laboratory with sufficient arrangement of testing facilities, appliances and laboratory technicians etc. at site and shall always co-operate in procurement of samples, conduction tests, as may be directed and no extra payment shall be made for them. Test samples shall be taken carefully in accordance with the I.S.I. method of sampling, no plea shall be entertained on this account. Job Mix Formula for B.M. and S.D.B.C. shall be done from any reputed authority by the contractor on his cost.

TESTING MATERIALS

All materials and workmanship shall be of the respective kind described in the contract and in the accordance with Engineer-in-charge instructions and shall be subjected from time to time to the testes mentioned under specifications. The contractor shall provide such assistance, labour and materials as are normally required for examining measuring and testing of the works and quantity weight or quality of materials used and shall supply materials, sufficiently in advance for testing as mentioned under specifications. The materials used subsequently for execution of the work shall strictly conform to the quality and sample approved. Necessary test for which facilities are not available locally or at site shall be conducted in the nearest available laboratory research institute, Lucknow or any other reputed technical institution. Cost of such testing and forwarding of sample to the laboratory etc. shall be borne by the contractor and nothing extra shall be paid on this account. Regular quality control test registers shall be maintained by the contractor.

ROYALTIES AND TAXES ETC.

The contractor shall pay all royalties, license fee, other charge at quarry, octroi duties, custom duties, toll taxes, trade tax and any other local taxes as may be levied. No passes for octroi or toll levied by local bodies on toll bridges shall be issued by the Department. Rate shall inclusive of the same. Nothing extra shall be paid due to fluctuations in the cost of materials, machines, bitumen, P.O.L., labour and all types of taxes etc.



TENDER DOCUMENT No.-159_19
लखनऊ विकास प्राधिकरण

COMPLIANCE WITH LOCAL BYE LAWS

The contractor shall throughout the continuance of the contract and in respect of all matters arising out of performance thereof, conform with all required regulating and bye-laws of the local or other authorities which may be applicable to the works.

ROAD TRANSPORT

The contractor employing motor vehicles for transport of material shall abide by provisions of the Motor Vehicles Act.

DAMAGES BY RAINS, ACCIDENTS OR NATURAL CALAMITIES

No payment will be made to the contractor for damage caused by rains, accidents or other natural calamities during the progress of work. No claim whatsoever shall be entertained on this account.

DEFAULT OF CONTACTOR IN COMPLIANCE

Constant defiance of the instructions of Engineer-in-charge on the part of the contractor or his authorized agent will make the contract liable to be terminated.

CLEARANCE OR SITE ON COMPLETION

The contractor shall at all times keep the premises free from accumulated waste materials or rubbish caused by his employees on the works and on completion of the work, he shall clear away and remove from site all surplus materials, rubbish and temporary work of any kind and fill up borrow pits dug by him. He shall leave whole of the site and work clean and in a workmanlike condition to the entire satisfaction of the Engineer-in-charge.



TENDER DOCUMENT No.-159_19
लखनऊ विकास प्राधिकरण

SCHEDULE – 'G'

**कार्य का नाम : अनंत नगर आवासीय योजना (मोहान रोड) के अन्तर्गत
ग्राम-कलियाखेड़ा स्थित मन्दिर के बाउण्ड्रीवाल का कार्य।**

S.No.	Item Description	Unit	Quantity	Rate (Rs.)
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m., All kinds of soil.	Cum	75.264	205.62
2	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift up to 1.5 m.	Cum	59.7	154.83
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :, 1:3:6 (1 Cement : 3 coarse sand(zone-III) derived from natural sources : 6 graded stone aggregate 20 mm nominal size derived from natural sources).	Cum	4.608	5,762.47
4	Providing and laying in position ready mixed or site batched design mix cement concrete for plain cement concrete work; using coarse aggregate and fine aggregate derived from natural sources, Portland Pozzolana/Ordinary Portland/Portland Slag cement, admixtures in recommended proportions as per IS : 9103 to accelerate/ retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; but excluding the cost of centering, shuttering and finishing as per direction of the Engineer-in-charge; for the following grades of concrete. Note : Extra cement upto 10% of the minimum specified cement content in design mix shall be payable separately. In case the cement content in design mix is more than 110% of the minimum specified cement content, the contractor shall have discretion to either re-design the mix or bear the cost of extra cement., All works up to plinth level:, Concrete of M25 grade with minimum cement content of 300 kg /cum	Cum	17.302	7,456.41
5	Providing and laying in position ready mixed or site batched design mix cement concrete for plain cement concrete work; using coarse aggregate and fine aggregate derived from natural sources, Portland Pozzolana/Ordinary Portland/Portland Slag cement, admixtures in recommended proportions as per IS : 9103 to accelerate/ retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; but excluding the	Cum	6.221	7,737.36



TENDER DOCUMENT No.-159_19
लखनऊ विकास प्राधिकरण

	cost of centering, shuttering and finishing as per direction of the Engineer-in-charge; for the following grades of concrete. Note : Extra cement upto 10% of the minimum specified cement content in design mix shall be payable separately. In case the cement content in design mix is more than 110% of the minimum specified cement content, the contractor shall have discretion to either re-design the mix or bear the cost of extra cement., All works above plinth and upto floor V level :, Concrete of M25 grade with minimum cement content of 300 kg /cum			
6	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.	Kg	2,736.00	71.5
7	Centering and shuttering including strutting, propping etc. and removal of form for :, Foundations, footings, bases of columns, etc. for mass concrete	Sqm	153.672	309.78
8	Brick work with non modular fly ash bricks conforming to IS:12894, class designation 10 average compressive strength in super structure above plinth level up to floor V level in :, Cement mortar 1:4 (1 cement : 4 coarse sand)	Cum	49	7,079.84

J.E.

A.E.

I/we here by offer to execute the above work on%
above/below (in figures)above/below (in
words).

Signature of Contractor

Name of Firm :

Address. :

Phone/Mobile No.: